

ଓଡ଼ିଶା ସରକାର



ପଞ୍ଚାୟତ୍ତରାଜ ଓ ପାଳିକାଗଣ ବିଭାଗ,  
ଓଡ଼ିଶା  
ପଞ୍ଚାୟତ ସମିତି କାର୍ଯ୍ୟାଳୟ: କୋଲାବିରା

**BIDS DOCUMENT FOR:-**

**Name of Work:** - Const. of Additional Class Room at  
Panchayat Samiti Degree College,  
Kolabira,  
Kolabira Block

**Tender Cost:** - Rs. 14,44,056 /-

## TENDER SCHEDULE

Name of the Work: Const. of Additional Class Room at Panchayat Samiti Degree College , Kolabira.

Tender Amount : Rs. 1444056 /- (Rupees Fourteen lakhs Forty Four Thousand Fifty Six ) only

Scheme:- CM Special Assistance ( Mukhyamantri Swantantra Sahayata )


ABSTARCT					
CONST.OF ADDL. CLASS ROOM (SMART CLASS) AT PS DEGREE COLLAGE, KOLABIRA UNDER KOLABIRA GP					
SL no	Items	Qty	Unit	Rate	Total
1	Earth work excavation in hard soil within Initial lead and initial lift including rough dressing and levelling the foudation bed and depositing the excavted earth away from work site etc.compelte	33.83	Cum	Rs. 206.80	Rs. 6,996.00
2	Filling foundation and plinth with well watered and rammed sand including all cost, conveyance and royalty of all materials etc.	39.92	Cum	Rs. 679.70	Rs. 27,133.00
3	CC(1:3:6) using 40 mm size CBG mental in foudation including all cost,conveyance, curing and royalty etc complete.	19.20	Cum	Rs. 5,594.10	Rs. 1,07,406.00
4	Fly ash bricks in cement mortar (1:6) in foundation and plinth including cost conveyance & royalty of the materials etc complete as per direction of the Engineer In Charge.	23.99	Cum	Rs. 4,846.90	Rs. 1,16,277.00
5	Fly ash bricks in cement mortar (1:6) in Superstructure including cost conveyance & royalty of the materials etc complete as per direction of the Engineer In Charge.	21.02	Cum	Rs. 4,880.20	Rs. 1,02,581.00
6	Labour for cutting,bending ,binding strengthing by the grills/M.S in position including cost of M.S rods cost.of binding wire 18 to 20 guage etc.complete	34.41	Qntl	Rs. 8,843.20	Rs. 3,04,294.00
7	RCC M 20 For RCC works using 12 mm size HBG chips including all cost,conveyance, curing and royalty etc complete.	34.41	Cum	Rs. 5,733.30	Rs. 1,97,282.00
8	20 mm thick C.P. in C.M.(1:4) for slab grading plaster including watering and curing and finishing including cost, conveyance royalty etc.	85.88	Sqm	Rs. 243.40	Rs. 20,903.00
9	Rigid and smooth centering and shuttering for R.C.C works				
	a) Plinth Bend	23.37	Sqm	Rs. 233.30	Rs. 5,452.00
	b) Lintal Bend	23.37	Sqm	Rs. 528.20	Rs. 12,344.00
	c) Chajjas & Slab	95.48	Sqm	Rs. 669.50	Rs. 63,923.00
	d) Beam & Column	72.00	Sqm	Rs. 471.00	Rs. 33,912.00
10	16 mm thick C.P. in C.M.(1:6) for brick work 12 mm deep including watering and curing and finishing including cost,conveyance royalty.	163.66	Sqm	Rs. 219.50	Rs. 35,923.00

Signature of Contractor

Block Development Officer, Kolabira

11	12 mm thick C.P. in C.M.(1:6) for brick work 12 mm deep including watering and curing and finishing including cost, conveyance royalty.	159.66	Sqm	Rs. 146.20	Rs. 23,342.00
12	Finishing wall surface of walls with Acrylic wall putty (Water based ) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc complete.	163.66	Sqm	Rs. 74.12	Rs. 12,130.00
13	Cost of MS Door & Windows	1294.20	kg	Rs. 100.00	Rs. 1,29,420.00
14	Painting two coats with approved paint on new iron work	63.18	Sqm	Rs. 152.50	Rs. 9,634.00
15	Supplying, Fitting and Fixing Vetrified tiles in Floors of Size (600x600) mm of Approved make on 20mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all materials. labour T&P etc required for the work all complete.	128.00	Sqm	Rs. 1,418.60	Rs. 1,81,580.00
16	Priming 1 coat with wall primer water bond cement primer including all labour, materials, T & P etc. complete	323.32	Sqm	Rs. 62.20	Rs. 20,110.00
17	Weather Coat two coats to walls with weather coat of approved hade on new work to give an even shade including cost of weather coat.	159.66	Sqm	Rs. 81.30	Rs. 12,980.00
18	Wall painting 2 coats with plastic emulsion paint of approved shade to give an even shade to the wall surface including cost of paint, labour, T & P for the item etc complete.	163.66	Sqm	Rs. 88.20	Rs. 14,434.00
				Total	Rs. 14,38,056.00
19	Add Cost Of Signboard				Rs. 6,000.00
	Total 19 (Nineteen ) Items			Total	Rs. 14,44,056.00

( Rupees Fourteen lakhs Forty Four Thousand Fifty Six )  
only

  
Junior Engineer  
KOLABIRA BLOCK

  
Asst. Executive Engineer  
KOLABIRA BLOCK

  
Block Development Officer  
KOLABIRA BLOCK

Signature of Contractor

Block Development Officer, Kolabira

My quoted rate is ..... % (both figure & word) Excess over / Less than / Equal to above estimated cost.

Note

1. The Contractor should not write anything except quoting of percentage and incase of anything regarding tender.
2. Strick out which are not applicable.

Total: - 19 (Nineteen) Items only

No. of correction:-

No. of overwriting:-

No. of Interpolation:-

Approved for 19 (Nineteen) Items only

Full Signature of the Contractor with date

**Block Development Officer  
Kolabira**

Signature of Contractor

Block Development Officer, Kolabira