

Name of work :- **Construction of Boundary wall for Protection of Government land at Balijudi (Nuapada)**

Contact No.:-

Bidder Name :-

Price Schedule						
This BOQ template must not be modified/replaced by the Bidder and the same should be uploaded after filling the relevant columns, as the Bidder is liable to be rejected for this tender, Bidders are allowed to enter the Bidder name and values only)						
Sl. No.	Item Description	Quantity	Unit	Estimate rate		Total Amount without Taxes
				Figure	words	
1	2	3	4	5	6	7
1	Earth work in excavation of foundation trenches in all kinds of soil including moorum, stoney earth and earth mixed with boulders except sheet rocks and boulders requiring blasting including dressing and leveling the bed upto the required depth and depositing the excavated materials with all leads and lifts T & P shoring & shuttering if required etc. complete.	105.00	Cum.	206.77	Two hundred six & seventy seven paise only	21710.85
2	Supplying filling in foundation and plinth with sand including watering ramming, cost, conveyance, royalties and all taxes of materials and cost of labour with T & P required for the work etc. complete (measurement will be taken on finished section only).	30.00	Cum.	535.48	five hundred thirty five & fourty eighty paise only	16064.40
3	Cement concrete (1:3:6) in foundation and floor i.e. below the base course of terrazzo flooring using 4 cm. (1½") size black hard hand broken granite stone metals of approved quality from approved quarry including lowering laying concrete watering and curing etc. complete to required level laid in layers not exceeding 0'-6" thick including cost, conveyance, royalties and all taxes of all materials and cost of all labour with T & P required for the work complete.	30.00	Cum.	5722.96	Five thousand seven hundred twenty two & ninty six paise only	171688.80
4	Fly Ash Brick masonry in cement mortar (1:6) in F&P with best quality bricks having crushing strength no less than 75 kg/sq.cm with dimensional tolerance +2% immersing the bricks in water for not less than 6 hours before use(the bricks shall be well burnt, free from cracks, well shaped,uniform in size and shall produce a clear ringing sound when struck) includes moulding, chamfering, corbelling etc. complete as per drawing, design and specification, watering and curing for seven days incl. cost , conveyance, and taxes of all materials, labour T&P etc. complete as directed by E.I.C.	31.50	Cum.	5118.58	Five thousand one hundred eighteen & fifty eight paise only	161235.27
5	2.5 C.m. D.P.C with cement concrete (1:2:4) using 12 mm. size hard broken granite chips	210.00	Sqm.	328.78	Three hundred Twenty eight & seventy eight paise only	69043.80

6	Fly Ash Brick masonry in cement mortar (1:6) in Super-structure with best quality bricks having crushing strength no less than 75 kg/sq.cm with dimensional tolerance + 2% immersing the bricks in water for not less than 6 hours before use(the bricks shall be well burnt, free from cracks, well shaped, uniform in size and shall produce a clear ringing sound when struck) includes moulding, chamfering, corbelling etc. complete as per drawing, design and specification, watering and curing for seven days incl. cost, conveyance, royalty and taxes of all materials, labour T&P etc. complete as directed by E.I.C.	168.90	Cum.	5203.10	Five thousand two hundred three & ten paise only	878803.59
7	12 mm (½") thick cement plaster (1:6) with neat cement punning in finished smooth brick walls and skirting after racking out the joints including watering and curing complete with cost conveyance royalties and all taxes of all materials and cost of all labour with T & P required for the work etc. complete.	876.89	Sqm.	156.70	One hundred fifty six & seventy paise only	137408.66
8	Providing 16 mm thick cement plaster to the inside surface of brick masonry wall with cement mortar (1:6) including racking out of joints, scraping and cleaning the surface with finishing the plaster surface smooth using wooden floats only to the proper plumbs and materials & all taxes, royalties, watering & curing etc. complete as directed by E.I.C	720.00	Sqm.	222.50	Two hundred Twenty two & fifty paise only	160200.00
9	Finishing walls with Cement Paint of approved shade in New work 2 coats to give an shade including cost of paint.	1596.89	Sqm.	33.47	Thirty three & fourty seven paise only	53447.91
10	Distemping two coats with any approved shade over a cost of Primer in the interior surface of walls etc complete in all floors as directed by the Engineer-in-Charge over a coat of chalk washing using distemper including cost conveyance of all materials including cost of distemper with all taxes and cost of all labour with T&P required for the work etc complete in all respect	1596.89	Sqm.	73.54	Seventy three & fifty four paise only	117435.29
11	Cleaning grass and removal of rubbish up to a distane of 50 meters outside the periphery of the area	0.08	Hectre	20883.77	Twenty thousand eight hundred eighty three & seventy seven paise only	1670.70
12	Costruction of Display board	1	Nos		Rs.	6000.00
	Total				Rs.	1794709.27

Say **1794709.00**

(Rupes Seventeen Lakhs ninty four thousand seven hundred nine) Only


 Junior Enineer
 Jharsuguda Block

 Assistant Exe. Engineer
 Jharsuguda Block


 Block Development Officer
 Jharsuguda Block

My/ our quoted rate is _____ % (both figure & words) excess over/ less than /equal to above estimated cost.

Signature of the tenderer

Notes:- (1) The contractor should not write any thing except quoting of percentage and in case of any thing else regarding tender rate mentioned, the tender is liable for rejection.

(2) Strike out which are not applicable.

Signature of the tenderer

Total-12 (Twelve) items only.

No. of Correction

No. of Overwriting

No. of Interpolation

Approved for - 12 (Twelve) Items only.

Signature of Contractor

Block Development Officer
Jharsuguda - 23

Block Development Officer
Jharsuguda Block - 23