

Tender Inviting Authority :-

Name of work :- **Construction of Boundary wall for Protection of Government land at Beherapat, H.Katapali**

Contact No.:-

Bidder Name :-

Price Schedule

This BOQ template must not be modified/replaced by the Bidder and the same should be uploaded after filling the relevant columns, else the Bidder is liable to be rejected for this tender, Bidders are allowed to enter the Bidder name and values only)

| Sl. No. | Item Description | Quantity | Unit | Estimate rate | | Total Amount without Taxes |
|---------|---|----------|------|----------------|---|----------------------------|
| | | | | Figure | words | |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| 1 | Earth work in excavation of foundation trenches in all kinds of soil including moorum, stoney earth and earth mixed with boulders except sheet rocks and boulders requiring blasting including dressing and leveling the bed upto the required depth and depositing the excavated materials with all leads and lifts T & P shoring & shuttering if required etc. complete. | 173.60 | Cum. | 206.77 | Two hundred six & seventy seven paise only | 35895.27 |
| 2 | Supplying filling in foundation and plinth with sand including watering ramming, cost, conveyance, royalties and all taxes of materials and cost of labour with T & P required for the work etc. complete (measurement will be taken on finished section only). | 49.60 | Cum. | 509.18 | Five hundred nine & eighty paise only | 25255.33 |
| 3 | Cement concrete (1:3:6) in foundation and floor i.e. below the base course of terrazzo flooring using 4 cm. (1½") size black hard hand broken granite stone metals of approved quality from approved quarry including lowering laying concrete watering and curing etc. complete to required level laid in layers not exceeding 0'-6" thick including cost, conveyance, royalties and all taxes of all materials and cost of all labour with T & P required for the work complete. | 49.60 | Cum. | 5596.70 | Five thousand five hundred ninty six & seventy paise only | 277596.32 |
| 4 | Fly Ash Brick masonry in cement mortar (1:6) in F&P with best quality bricks having crushing strength no less than 75 kg/sq.cm with dimensional tolerance +2% immersing the bricks in water for not less than 6 hours before use(the bricks shall be well burnt, free from cracks, well shaped,uniform in size and shall produce a clear ringing sound when struck) includes moulding, chamfering, corbelling etc. complete as per drawing, design and specification, watering and curing for seven days incl. cost , conveyance, and taxes of all materials, labour T&P etc. complete as directed by E.I.C. | 52.08 | Cum. | 5118.58 | Five thousand one hundred eighteen & fifty eight paise only | 266575.65 |
| 5 | 2.5 C.m. D.P.C with cement concrete (1:2:4) using 12 mm. size hard broken granite chips | 347.20 | Sqm. | 325.76 | Three hundred Twenty five & seventy six paise only | 113103.87 |

| | | | | | | |
|----|---|---------|--------|-----------------|---|-------------------|
| 6 | Fly Ash Brick masonry in cement mortar (1:6) in Super-structure with best quality bricks having crushing strength no less than 75 kg/sq.cm with dimensional tolerance + 2% immersing the bricks in water for not less than 6 hours before use(the bricks shall be well burnt, free from cracks, well shaped, uniform in size and shall produce a clear ringing sound when struck) includes moulding, chamfering, corbelling etc. complete as per drawing, design and specification, watering and curing for seven days incl. cost , conveyance, royalty and taxes of all materials, labour T&P etc. complete as directed by E.I.C. | 279.26 | Cum. | 5203.10 | Five thousand two hundred three & ten paise only | 1453017.71 |
| 7 | 12 mm (½") thick cement plaster (1:6) with neat cement punning in finished smooth brick walls and skirting after racking out the joints including watering and curing complete with cost conveyance royalties and all taxes of all materials and cost of all labour with T & P required for the work etc. complete. | 1449.78 | Sqm. | 156.70 | One hundred fifty six & seventy paise only | 227180.53 |
| 8 | Providing 16 mm thick cement plaster to the inside surface of brick masonry wall with cement mortar (1:6) including racking out of joints, scraping and cleaning the surface with finishing the plaster surface smooth using wooden floats only to the proper plumbs and materials & all taxes, royalties, watering & curing etc. complete as directed by E.I.C | 1190.40 | Sqm. | 222.50 | Two hundred Twenty two & two paise only | 264864.00 |
| 9 | Finishing walls with Cement Paint of approved shade in New work 2 coats to give an shade including cost of paint. | 2640.18 | Sqm. | 33.47 | Thirty three & fourty seven paise only | 88366.82 |
| 10 | Distempering two coats with any approved shade over a cost of Primer in the interior surface of walls etc complete in all floors as directed by the Engineer-in-Charge over a coat of chalk washing using distemper including cost conveyance of all materials including cost of distemper with all taxes and cost of all labour with T&P required for the work etc complete in all respect | 2640.18 | Sqm. | 73.54 | Seventy three & fifty four paise only | 194158.84 |
| 11 | Cleaning grass and removal of rubbish up to a distane of 50 meters outside the periphery of the area | 0.12 | Hectre | 20883.77 | Twenty thousand eight hundred eighty three & seventy seven paise only | 2506.05 |
| 12 | Costruction of Display board | 1 | Nos | | Rs. | 6000.00 |
| | Total | | | | Rs. | 2954520.38 |

Say **2954520.00**

(Rupes Twenty nine Lakhs fifty four thousand five hundred twenty) Only


Junior Engineer
Jharsuguda BlockAssistant Exe. Engineer
Jharsuguda BlockBlock Development Officer
Jharsuguda Block


My/ our quoted rate is _____ % (both figure & words) excess over/ less than /equal to above estimated cost.

Signature of the tenderer

Notes:- (1) The contractor should not write any thing except quoting of percentage and in case of any thing else regarding tender rate mentioned, the tender is liable for rejection.

(2) Strike out which are not applicable.

Signature of the tenderer

Total-12 (Twelve) items only.

No. of Correction

No. of Overwriting

No. of Interpolation

Approved for - 12 (Twelve) Items only.

Signature of Contractor


Block Development Officer
Jharsuguda
5.7.23


Block Development Officer
Jharsuguda Block
5.7.23