

Percentage BoQ

Tender Inviting Authority: BDO, Lakhanpur

Name of Work: Const of Smart Class Room At Kumharbandh Higher Secondary School

Bidder	
--------	--

PRICE SCHEDULE

(this BOQ templete must be modified/ replaced by the bidder and the same should be uploaded after filling the relevant coulumns, else the bidder is llable to be rejected for this tender . Bidders are allowed to enter the Bidder Name and Values only)

Number	Text#	Number#	Text#	Number#	Number#	Text#
Sl. No.	Item Description	Quantity	Units	Estimated Rate	Total Amount Without Taxes	Total Amount in Words
1	Earth work in excavation in foundation in all kinds of soil with all leads and lifts including dressing and levelling the bed in layers not exceeding 0.3 m in depth including dewatering if necessary with cost of all labour and T & P work etc. Complete as per direction of Engineer-in-charge					
	Const of Smart Class Room At Kumharbandh Higher Secondary School	23.49	cum	206.77	0.00	
2	Supplying filling in F & P with clean course good river sand including watering, ramming, poking & compacting & cost, conveyance royalties, taxes of all materials, labour, T & P etc. Complete as per direction of Engineer-in-Charge					
	Const of Smart Class Room At Kumharbandh Higher Secondary School	22.82	cum	1028.74	0.00	
3	Providing and laying PCC of (1:3:6) with 2.5cm to 4cm size crusher broken hard black granite metal with cost, conveyance, royalties, taxes of all materials, all labour, T & P etc. Complete as per direction of Engineer-in-charge					
	Const of Smart Class Room At Kumharbandh Higher Secondary School	12.04	cum	5565.35	0.00	

4	Providing and laying RCC work in M-25 grade with 20mm and down grade black hard granite crusher broken stone chips of approved quality from quarry with smooth centering and shuttering hoisting and laying in layers including cost. Conveyance, royalty and taxes of all materials, labour, T & P etc. complete as per direction of the Engineer-in-charge					
	1st Floor RCC Work					
	Const of Smart Class Room At Kumharbandh Higher Secondary School	17.12	Cum	6604.86	113042.00	
5	Providing MS Reinforcement for RCC work including cutting, bending, binding & tying the grills & placing in position with cost of MS Rod and binding wire of 18 to 20 gauge including cost of all materials, labour, T & P etc. Complete as per direction of the Engineer-in-Charge (G. Floor)					
	Const of Smart Class Room At Kumharbandh Higher Secondary School	15.40	Qnt.	8580.44	132169.00	
6	Brick work with Fly Ash bricks of size 23cmX11cmX8cm and crushing strength not less than 75kg/cm ² in C.M.(1:6) in foundation and plinth including all charges					
	Const of Smart Class Room At Kumharbandh Higher Secondary School	10.89	Cum	4860.80	0.00	
7	Brick work with Fly Ash bricks of size 23cmX11cmX8cm and crushing strength not less than 75kg/cm ² in C.M.(1:6) in super structure including all charges (G. Floor)					
	Const of Smart Class Room At Kumharbandh Higher Secondary School	18.51	Cum	5279.84	97732.00	
8	Rigid and smooth centring and shuttering for RCC work including false works and dismantling them after casting including cost material					
	COLUMN BASE & PLINRH BEAM & COLUMN & BEAM	67.85	Sqm	1030.11	69892.00	
	LINTEL BEAM	10.74	Sqm	632.91	6801.00	
	ROOF SLAB & CHAJJA	82.03	Sqm	738.59	60587.00	

9	Providing 16 mm thick cement plaster in CM (1:6) finished smooth to inside surface including cost conveyance, royalty, taxes of all materials, labour, T & P etc. complete as per direction of Engineer-in-Charge (G.Floor)					
	Const of Smart Class Room At Kumharbandh Higher Secondary School	224.40	Sqm	232.62	52201.00	
10	12MM thick cement plaster (1:6) to RCC for brick masonry including all cost (G.Floor)					
	Const of Smart Class Room At Kumharbandh Higher Secondary School	147.50	Sqm	170.41	25136.00	
11	Supplying fitting and fixing vetrified tile in floors of size 600mmX 600mm of approved make confirming to IS 13755 laid on 20mm thick cement mortar (1:4) (1cement:4course sand) and filling joints with white cement of approved quality including cost of all materials, labour T & P etc required for the work all complete as per direction of the Engineer-in-Charge (For new work only)					
	Const of Smart Class Room At Kumharbandh Higher Secondary School	94.23	Sqm	1347.81	126971.00	
12	Finishing Surface Of Walls With Cement Based Wall Putty & Making Smooth To Recive Painting Including Cost Of Scaffolding Etc. With Cost Of All Material & Labour					
	Const of Smart Class Room At Kumharbandh Higher Secondary School	455.07	Sqm	77.53	37744.00	
13	Fixing of Tiles in Dados skirting ands rised including cost conveyance & Royalty					
	Const of Smart Class Room At Kumharbandh Higher Secondary School	7.28	sqm	1462.83	10618.00	
14	Painting two coats with water proofing Weather coats of approved shade including cost of paint (G.Floor)					
	Const of Smart Class Room At Kumharbandh Higher Secondary School	2593.71	Sqm	85.98	222997.00	

15	Supplying fitting fixing of Aluminium penal Door shutters including transport taxes of all materials in G. Floor					
	Const of Smart Class Room At Kumharbandh Higher Secondary School	8.36	Sqm	5103.30	0.00	
16	2.5 cm thick Grading concret cc (1:2:2)					
	Const of Smart Class Room At Kumharbandh Higher Secondary School	81.12	sqm	368.21	29869.00	
17	Painting two coat with enamel paint over primer one coat with ready mixed zink yellow primer of approved quality					
	Const of Smart Class Room At Kumharbandh Higher Secondary School	72.55	sqm	221.33	16059.00	
18	manufacture supplying fitting fixing of MS Door & Window					
	Const of Smart Class Room At Kumharbandh Higher Secondary School	413.87	KG	90.00	37248.00	
19	Add Towards cost of Display Board				3000.00	
				Total	1042066.00	

Rupees ten lakhs forty two thousand sixty six only


As per Estt 1042066.00
Extra 0.00


Assistant Executive Engineer
Lakhanpur Block


AE/JE/GPTA
Lakhanpur Block

Approved for 19 (Ninteen) items only

My/our quoted rate is % (both in


Signature of tenderer
15/7/23

NOTES :-

1. The contractor should not write anything excepting quoting of percentage and in any case
2. Percentage quoted by the tenderer shall be accurately filled in words and in figures..
3. Strike out which is not applicable. If the tenderer quotes the percentage without mentioning
4. Percentage should be quoted up to (one) digit after the decimal point. If the tenderer writes
5. Rate of all items are inclusive of cost, carriage, royalty, cess and other taxes of materials.

Tenderer

No. of corrections.....

No. of Over writings.....

No. of Interpolations.....

Contractor

Block Development Officer

Block Development Office

LAKHANPUR