

BILL OF QUANTITY**Construction of Additional Class room at Laikera Degree College,
First Floor**

Sl. No.	Item of Work	Quantity to be	Unit	Rate		Amount
				Figure	words	
1	2	3	4	5	6	
1	Brick work with Fly ash bricks (23Cm.x11Cm.x8Cm.) size having crushing strength not less than 75 Kg/Cm2 with dimensional tolerance \pm 2% in cement mortar (1:6) in super structure including splays, cuttings, circular moldings, watering & curing for 7 days, cost, conveyance, taxes & royalties of all materials, labour with T&P etc. complete in all respect.	22.18	one cum	5402.4	Rupees Five Thousand Four Hundred Two And Paise Forty Only	119825.00
2	R.C.C. M20 with crushed Granite 20 mm down grade coarse aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by vibrators in layers not exceeding 0.15 meter in depth including watering, curing for required period of 28 days, including cost, conveyance and royalty and other taxes of all materials, T& P materials required for this item including hire and running charges of machineries complete, including centering & shuttering as directed by the Engineer-in-charge.				Rupees Nil	
(a)	Lintal Band, Window Sill.Wall Beam.	3.87	one cum	14890.60	Rupees Fourteen Thousand Eight Hundred Ninety And Paise Sixty Only	57627.00
©	Coloumn & Beam	3.23	one cum	18125.60	Rupees Eighteen Thousand One Hundred Twenty Five And Paise Sixty Only	58546.00



A. E



Block Development Officer
LAIKERA



A. E. C.

3	R.C.C. M25 with crushed Granite 20 mm down grade coarse aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by vibrators in layers not exceeding 0.15 meter in depth including watering, curing for required period of 28 days, including cost, conveyance and royalty and other taxes of all materials, T & P materials required for this item including hire and running charges of machineries complete, including centering & shuttering as directed by the Engineer-in-charge.				Rupees Nil	
(a)	Roof slab & Chajja	13.570	one cum	14411.00	Rupees Fourteen Thousand Four Hundred Eleven Only	195557.00
4	HYSD steel (TISKON/SAIL/JSW) and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC work including cost, conveyance and taxes of MS rods or HYSD steel and binding wires of 18-20 gauge and labour charges required for the work etc. complete in all floors.	20.66	One Quintal	9205.60	Rupees Nine Thousand Two Hundred Five And Paise Sixty Only	190188.00
5	12 mm thick cement plaster (1:6) finished smooth to brick masonry with cement punning for skirting after racking out joints including watering, curing including cost, conveyance, taxes, royalties & labour with T&P etc. complete.	141.060	One square meter	163.20	Rupees One Hundred Sixty Three And Paise Twenty Only	23021.00
6	16 MM (5/8") thick cement plaster in C.M.(1:6) finishing smooth to inside rough surface of 9" X 10" thick brick walls after racking out the joints including watering and curing with cost, conveyance, royalty and taxes of all materials and cost of all labour charges, cess required for the work etc. complete.	215.39	One square meter	228.50	Rupees Two Hundred Twenty Eight And Paise Fifty Only	49217.00
7	6mm thick cement plaster in cm (1:4) finished smooth to brick masonry including racking out joints including watering, curing, cost, conveyance, taxes, royalties, labour with T&P etc. complete in all respect.	117.870	One square meter	174.70	Rupees One Hundred Seventy Four And Paise Seventy Only	20592.00


A.E



Block Development Officer
LAKHRA


A.E.F

8	Fixing V.Tiles Printed Serise (KAJARIA/SOMANI) (600*600) MMin floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1cement : 1sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including rubbing and polishing complete	86.54	One square meter	1442.20	Rupees One Thousand Four Hundred Forty Two And Paise Twenty Only	124808.00
9	Fixing of V. tiles Printed Serise (KAJARIA/SOMANI) (600*600) MM in dados skirting & riser of steps on 12mm thick cement plaster 1:3 joined with neat cement slurry mixed with pigments to match the shade of the tiles, including rubbing & polishing etc. complete including cost, conveyance, taxes & royalties of all materials,	3.67	One square meter	1709.55	Rupees One Thousand Seven Hundred Nine And Paise Fifty Five Only	6274.00
10	Fixing of Ceramic wall tiles Printed Serise (KAJARIA/SOMANI) (20*30) CM in dados skirting & riser of steps on 12mm thick cement plaster 1:3 joined with neat cement slurry mixed with pigments to match the shade of the tiles, including rubbing & polishing etc. complete including cost, conveyance, taxes & royalties of all materials,	18.88	One square meter	1405.30	Rupees One Thousand Four Hundred Five And Paise Thirty Only	26532.00
11	Supplying fitting & fixing of prefabricated M.S. doors & windows including cost of all materials & labour with T&P etc. complete.(As per actual)	728.39	one kg	100.00	Rupees One Hundred Only	72839.00
12	Labour for fitting & fixing of prefabricated M.S. doors & windows including cost of all labour etc. complete.	7.28	one Qtl.	580.80	Rupees Five Hundred Eighty And	4228.00
13	Supplying, fitting , fixing up window (sliding type) made up aluminium section 151-154, 151-155, as windows frame section No. 151-155, 151-153, and 151-167 as shutter frame with 5mm thickblack glass as pannel fitted with rubber beading includinglocking arrangement including all fitting including cost of materialsall taxes, labour,T7P etc. complete as per the direction of engineer in charge.	7.43	One square meter	6594.50	Rupees Six Thousand Five Hundred Ninety Four And Paise Fifty Only	48997.00
14	Providing fitting and fixing of false celing with aluminium anodized T section No.3215 with 2'0" centre to centre,Lsection No.1705 up to 15 micronon 4walls to be fixed by means of steel screw and P.V.C plug and thealuminium grid 2'0"x2'0" with gypsum board suspended from from celing etc. complete.	58.55	one sqm	1210.90	Rupees One Thousand Two Hundred Ten And Paise Ninety Only	70898.00
15	Painting 2 coats to over 1 coat of priming with ready mixed Zinc chromate yellow primer of approved brand on Iron works of MS doors, windows and grills, with all cost of paint, brush, etc, labour, cess etc complete.	40.100	One square meter	220.40	Rupees Two Hundred Twenty And Paise Forty Only	8838.00


A.E.

Block Development Officer
LAKKESHA


A.E.F.

16	White washing one coats to wall surface including cost of all materials and labour with T&P etc complete in all respect.				Rupees Nil	
(a)	Ground Floor	1596.940	One square meter	21.30	Rupees Twenty One And Paise Thirty Only	34015.00
(b)	First Floor	141.060	One square meter	21.90	Rupees Twenty One And Paise Ninety Only	3089.00
17	Finishing wall surface with Acrylic wall putty of approved make & finished smooth & even surface to receive painting including cost of scaffolding staging charges with cost of all materials, taxes, labour with T&P etc. complete in all floors.	333.26	One square meter	78.95	Rupees Seventy Eight And Paise Ninety Five Only	26311.00
18	Wall Priming one coat with any approved primer on New Plastered surface of with any approved primer including cost of primer	333.26	One square meter	63.50	Rupees Sixty Three And Paise Fifty Only	21162.0
19	Distemping two coats to wall surface with Distemper of app. Shade including cost of all materials and labour with T&P etc complete in all respect.	333.26	One square meter	74.10	Rupees Seventy Four And Paise Ten Only	24695.00
20	Finishing walls with plastic emulsion paint of approved shade on new work(two coats)				Rupees Nil	
(a)	Ground Floor	4.500	One square	88.20	Rupees Eighty Eight And Paise	397.00
(b)	First Floor	141.060	One square	89.90	Rupees Eighty Nine And Paise	12681.00
21	Provision for Transparency Board					5,000.00
GRAND TOTAL						1,205,337.00

(RUPEES TWELVE LAKH FIVE THOUSAND THREE HUNDRED & THIRTY SEVEN) ONLY.

Approved

 Asst. Executive Engineer
 Laikera Block


 Block Development Officer
 LAIKERA

APPROVED FOR 21 (TWENTY ONE) ITEMS ONLY.


My/our quoted rate is % (both in figures and

Signature of Tenderer

NOTES :-

1. The contractor should not write anything excepting quoting of percentage and in any case anything else
2. Percentage quoted by the tenderer shall be accurately filled in words and in figures..


 A.E.


 Block Development Officer
 LAIKERA


 A.E.

3. Strike out which is not applicable. If the tenderer quotes the percentage without mentioning excess or
4. Percentage should be quoted up to (one) digit after the decimal point. If the tenderer writes more than 1
5. Rate of all items are inclusive of cost, carriage, royalty, cess and other taxes of materials.

Tenderer

No. of corrections.....

No. of Over writings.....

No. of Interpolations.....

Contractor


Block Development Officer
Block Development Office
Lalkera
LAIKERA


A.B.E.