

BILL OF QUANTITY

Renovation of Higher Secondary School, Laikera

| Sl. No. | Item of Work | Quantity to be | Unit | Rate | | Amount |
|---------|---|----------------|---------|----------|--|----------|
| | | | | Figure | words | |
| | | 3 | 4 | | 5 | 6 |
| 1 | 2 | 6.21 | one cum | 1203.57 | Rupees One Thousand Two Hundred Three And Paise Fifty Seven Only | 7474.00 |
| 1 | Dismantling brick or stone masonry in lime or cement mortar under 3m. height including stacking the useful materials for reuse and removing the debris within 50m. Lead | | | | | |
| 2 | Brick work with Fly ash bricks (23Cm.x11Cm.x8Cm.) size having crushing strength not less than 75 Kg/Cm2 with dimensional tolerance $\pm 2\%$ in cement mortar (1:6) in foundation & plinth including splays, cuttings, circular moldings, watering & curing for 7 days, cost, conveyance, taxes & royalties of all materials, labour with T&P etc. complete in all respect. | 2.55 | one cum | 5114.71 | Rupees Five Thousand One Hundred Fourteen And Paise Seventy One Only | 13043.00 |
| 3 | R.C.C. M20 with crushed Granite 20 mm down grade coarse aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by vibrators in layers not exceeding 0.15 meter in depth including watering, curing for required period of 28 days, including cost, conveyance and royalty and other taxes of all materials, T& P materials required for this item including hire and running charges of machineries complete, including centering & shuttering as directed by the Engineer-in-charge. | | | | Rupees Nil | |
| (a) | Mass concrete | 3.40 | one cum | 6843.24 | Rupees Six Thousand Eight Hundred Forty Three And Paise Twenty Four Only | 23267.00 |
| (b) | Lintal Band | 0.15 | one cum | 13317.21 | Rupees Thirteen Thousand Three Hundred Seventeen And Paise Twenty One Only | 1998.00 |

A. E. Laikera

Block Development Officer
LAIKERA

A. E. E.

| | | | | | | |
|----|--|--------|------------------|---------|--|-----------|
| 4 | HYSD steel (SAIL/TISCON/JSW) and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC work including cost, conveyance and taxes of MS rods or HYSD steel and binding wires of 18-20 gauge and labour charges requires for the work etc. complete in all floors. | 2.84 | One Quintal | 9221.41 | Rupees Nine Thousand Two Hundred Twenty One And Paise Forty One Only | 26189.00 |
| 5 | 12 mm thick cement plaster (1:6) finished smooth to brick masonry with cement punning for skirting after racking out joints including watering, curing including cost, conveyance, taxes, royalties & labour with T&P etc. complete. | 28.98 | One square meter | 157.29 | Rupees One Hundred Fifty Seven And Paise Twenty Nine Only | 4558.00 |
| 6 | 16 MM (5/8") thick cement plaster in C.M.(1:6) finishing smooth to inside rough surface of 9" X 10" thick brick walls after racking out the joints including watering and curing with cost, conveyance, royalty and taxes of all materials and cost of all labour charges, cess required for the work etc. complete. | 11.15 | One square meter | 225.91 | Rupees Two Hundred Twenty Five And Paise Ninety One Only | 2519.00 |
| 7 | 6mm thick cement plaster in cm (1:4) finished smooth to brick masonry including racking out joints including watering, curing, cost, conveyance, taxes, royalties, labour with T&P etc. complete in all respect. | 598.37 | One square meter | 150.45 | Rupees One Hundred Fifty And Paise Forty Five Only | 90025.00 |
| 8 | Provision for cost of I-section steel beam(ISMB 200 x100) | 20.42 | one Qtl. | 8200.00 | Rupees Eight Thousand Two Hundred Only | 167444.00 |
| 9 | Labour charges for fitting & fixing of I-section steel beams. | 20.42 | one Qtl. | 882.08 | Rupees Eight Hundred Eighty Two And Paise Eight Only | 18012.00 |
| 10 | Providing wire mesh in Celing Plaster including cost of wire mesh, Iron nail , Labour charges etc. complete | | | | Rupees Nil | |
| a) | Wire Mesh | 300.00 | one sqm | 201.41 | Rupees Two Hundred One And Paise Forty One Only | 60423.00 |
| b) | Steel Nail | 15.00 | One Kg. | 79.56 | Rupees Seventy Nine And Paise Fifty Six Only | 1193.00 |
| c) | Labour charges | | L.S. | | Rupees Nil | 4000.00 |


A.E.

Block Development Officer
LAKHNA


A.E.

| | | | | | | |
|----|---|--------|------------------|---------|--|-----------|
| 11 | Providing fitting and fixing of false ceiling with aluminium anodized T section No.3215 with 2'0" centre to centre, Lsection No.1705 up to 15 micronon 4walls to be fixed by means of steel screw and P.V.C plug and thealuminium grid 2'0"x2'0" with gypsum board suspended from from ceiling etc. complete. | 312.14 | one sqm | 1210.85 | Rupees One Thousand Two Hundred Ten And Paise Eighty Five Only | 377960.00 |
| 12 | Finishing wall surface with Acrylic wall putty of approved make & finished smooth & even surface to receive painting including cost of scaffolding staging charges with cost of all materials, taxes, labour with T&P etc. complete in all floors. | 987.76 | One square meter | 77.50 | Rupees Seventy Seven And Paise Fifty Only | 76551.00 |
| 13 | Fixing V.Tiles Printed Serise (KAJARIA/SOMANI) (600*600) MM in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1cement : 1sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of precast tiles per 1 sqm | 541.98 | One square meter | 1552.50 | Rupees One Thousand Five Hundred Fifty Two And Paise Fifty Only | 841424.00 |
| 14 | Fixing of V. tiles Printed Serise (KAJARIA/SOMANI) (40*40) CM in dados skirting & riser of steps on 12mm thick cement plaster 1:3 jointed with neat cement slurry mixed with pigments to match the shade of the tiles, including rubbing & polishing etc. complete including cost, conveyance, taxes & royalties of all materials, labour with T&P complete in all respect. | 112.04 | One square meter | 1586.60 | Rupees One Thousand Five Hundred Eighty Six And Paise Sixty Only | 177763.00 |
| 15 | Fixing M.Tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1cement : 1sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including rubbing and polishing complete excluding cost of marble tiles per 1 sqm | 11.15 | One square meter | 1367.57 | Rupees One Thousand Three Hundred Sixty Seven And Paise Fifty Seven Only | 15248.00 |
| 16 | Fixing of Matble tiles in dados skirting & riser of steps on 12mm thick cement plaster 1:3 jointed with neat cement slurry mixed with pigments to match the shade of the marble tiles, including rubbing & polishing etc. complete including cost, conveyance, taxes & royalties of all materials, labour with T&P complete in all respect. | 5.57 | One square meter | 1418.44 | Rupees One Thousand Four Hundred Eighteen And Paise Forty Four Only | 7901.00 |


A. E.


Block Development Officer
L.P.S.


A.B.E.

| | | | | | | |
|----|---|---------|------------------|---------|--|-----------|
| 17 | Supplying, fitting afixing of stainless steel of 304 grade in hand railing in all floors using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost conveyance, taxes of all materials labour, T&P etc. required for the complete in all respect. | 8.23 | per mtr | 3518.57 | Rupees Three Thousand four hundred ninety nine and paisa fifty five only | 28958.00 |
| 18 | Supplying, fitting , fixing up window (sliding type) made up aluminium section 151-154, 151-155, as windows frame section No. 151-155, 151-153, and 151-167 as shutter frame with 5mm thickblack glass as pannel fitted with rubber beading includinglocking arrangement including all fitting including cost of materialsall taxes, labour,T7P etc. complete as per the direction of engineer in charge. | 60.20 | One square meter | 6594.50 | Rupees Three Thousand four hundred ninety nine and paisa fifty five only | 396999.00 |
| 19 | Wall Priming one coat with any approved primer on new plasterwd surface including cost of primer etc. per sqm. | 1663.99 | One square meter | 60.90 | Rupees Three Thousand four hundred ninety nine and paisa fifty five only | 101337.00 |
| 20 | Distempering two coats to wall surface with Distemper of app. Shade including cost of all materials and labour with T&P etc complete in all respect. | 1663.99 | One square meter | 75.10 | Rupees Three Thousand four hundred ninety nine and paisa fifty five only | 124966.00 |
| 21 | Finishing walls with plastic emulsion paint of approved shade on new work(two coats) | 269.55 | One square meter | 92.90 | Rupees Three Thousand four hundred ninety nine and paisa fifty five only | 25041.00 |


 A.E. Laikera
 Block Development Officer
 LAIKERA

 A.G.E.

| | | | | | | |
|-------------|---|--------|------------------|--------|--|--------------|
| 22 | Painting 2 coats to over 1 coat of priming with ready mixed Zinc chromate yellow primer of approved brand on Iron works of MS doors, windows and grills, with all cost of paint, brush, etc, labour, cess etc complete. | 196.14 | One square meter | 154.50 | Rupees Three Thousand four hundred ninety nine and paisa fifty five only | 30304.00 |
| 23 | Provision for Transparency Board | | | | | 5,000.00 |
| GRAND TOTAL | | | | | | 2,629,597.00 |

(RUPEES TWENTY SIX LAKH TWENTY NINE THOUSAND FIVE HUNDRED & NINETY SEVEN) ONLY.

Approved

 Asst. Executive Engineer
 Laikera Block


 Block Development Officer
 LAIKERA

APPROVED FOR 23 (TWENTY THREE) ITEMS ONLY.

My/our quoted rate is % (both in figures and

Signature of Tenderer

NOTES :-

1. The contractor should not write anything excepting quoting of percentage and in any case anything else
2. Percentage quoted by the tenderer shall be accurately filled in words and in figures..
3. Strike out which is not applicable. If the tenderer quotes the percentage without mentioning excess or
4. Percentage should be quoted up to (one) digit after the decimal point. If the tenderer writes more than 1
5. Rate of all items are inclusive of cost, carriage, royalty, cess and other taxes of materials.

Tenderer

No. of corrections.....
 No. of Over writings.....
 No. of Interpolations.....

Contractor


 Block Development Officer
 Laikera
 LAIKERA


 A. E. Laikera.