

TENDER SCHEDULE

Sold to Sri..... Class of contractor on payment of

Rs. (Rupees) only vide Bank Draft No.

..... Dated.....

**Block Development Officer
Kolabira**

TENDER SCHEDULE

| | | |
|-----------|---|---|
| 1 | Name of Work | Completion of Mukshya Mantri Sabha Ghar at Paikpada of Raghunathpali G.P |
| 2 | Name of the Scheme | WODC-2023-24 |
| 3 | Estimated cost | Rs.2073000/- |
| 4 | Amount Put to Tender | Rs.14,35,243.50/- |
| 5 | Earnest Money Deposit E.M.D. (1%) | Rs.14,352/- |
| 6 | Class of Contractor | "C" and " D" Class |
| 7 | Cost of tender paper | Rs. 6000/- |
| 8 | Period of completion | Six calander months |
| 9 | Last Date of Sale of tender paper | 24-11-2023 upto 4.00 PM |
| 10 | Last Date and Time of receipt of tender paper | 24-11-2023 upto 4.00 PM |
| 11 | Date and Time of opening of tender paper | 28-11-2023 at 11.00 AM |

ABSTARCT

COMPL.OF MUKHYA MANTRI SABHA GHAR AT PAIKPADA, RAGHUNATHPALI GP

| SL no | Items | Qty | Unit | Rate | Total |
|-------|---|--------|------|--------------|----------------|
| 1 | Fly ash bricks in cement mortar (1:6) in Superstructure including cost conveyance & royalty of the materials etc complete as per direction of the Engineer In Charge. | 27.92 | Cum | Rs. 4,879.30 | Rs. 136230 .00 |
| 2 | Labour for cutting,bending ,binding strengthening by the grills/M.S in position including cost of M.S rods cost.of binding wire 18 to 20 guage etc.complete | 35.34 | Qntl | Rs. 8843.2 | Rs. 312555.00 |
| 3 | RCC.M 20 For RCC works using 12 mm size HBG chips including all cost,conveyance, curing and royalty etc complete. | 38.13 | Cum | Rs. 5,733.30 | Rs. 218592.00 |
| 4 | 20 mm thick C.P. in C.M.(1:4) for slab grading plaster including watering and curing and finishing including cost, conveyance royalty etc. | 33.68 | Sqm | Rs. 231.30 | Rs. 7790.00 |
| 5 | Rigid and smooth centering and shuttering for R.C.C works | | | | |
| | a) Plinth Bend | 0 | Sqm | Rs. 0 | Rs. 0 |
| | b) Lintal Bend | 32.47 | Sqm | Rs. 528.20 | Rs. 17148.00 |
| | c) Chajjas & Slab | 197.46 | Sqm | Rs. 669.50 | Rs. 132198.00 |
| | d) Beam & Column | 113.64 | Sqm | Rs. 1009.2 | Rs. 114690.00 |
| 6 | 16 mm thick C.P. in C.M.(1:6) for brick work 12 mm deep including watering and curing and finishing including cost,conveyance royalty. | 188.66 | Sqm | Rs. 219.50 | Rs. 41411.00 |
| 7 | 12 mm thick C.P. in C.M.(1:6) for brick work 12 mm deep including watering and curing and finishing including cost, conveyance royalty. | 156.17 | Sqm | Rs. 146.20 | Rs. 22831.00 |

Full Signature of Contractor

Block Development Officer
Kolabira

| | | | | | |
|--------------------------------|--|--------|-----|--------------|-----------------|
| 8 | Finishing wall surface of walls with Acrylic wall putty (Water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc complete | 188.66 | Sqm | Rs. 136.30 | Rs. 25714.00 |
| 9 | Cost of MS Door & Windows | 783.6 | kg | Rs. 90 | Rs. 70524.00 |
| 10 | Supplying ,fitting,fixing up window(sliding type)made up aluminium Section 9778,as windows frame section No.4095,4096 and 9777,3994 as shutter frame with 5mm thick | 79.95 | kg | Rs. 670.9 | Rs. 53638.00 |
| 11 | Supplying,Fitting and Fixing Vetrified tiles in Floors of Size (600x600) mm of Approved make on 20mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all materials.labour T&P etc required for the work all complete. | 143.37 | Sqm | Rs. 1,579.31 | Rs. 226430.00 |
| 12 | Fixing tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3)jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing | 4.62 | Sqm | Rs. 1579.31 | Rs. 7296.00 |
| 13 | Weather Coat two coats to walls with weather coat of approved hade on new work to give an even shade including cost of weather coat. | 189.88 | Sqm | Rs. 81.30 | Rs. 15437.24 |
| 14 | Wall painting 2 coats with plastic emulsion paint of approved shade to give an even shade to the wall surface including cost of paint, labour , T & P for the item etc complete. | 188.68 | Sqm | Rs. 88.20 | Rs. 16639.81 |
| 15 | Plain Glass | 16.35 | Sqm | Rs. 680.0 | Rs. 11118.00 |
| 16 | Add Cost Of Signboard | | | | Rs. 5000/- |
| Total Items 16 (Sixteen) only | | | | Total | Rs. 14,35243.50 |

(Rupees Fourteen Lakhs Thirty Five Thousand Two Hundred Forty Three) only

| | | | | | |
|-------------------------------------|--|--|--|--|--|
| G.S.T 18% will be paid extra | | | | | |
|-------------------------------------|--|--|--|--|--|

Full Signature of Contractor

Block Development Officer
Kolabira

| | |
|---|------------------|
| Rate to be Quoted in terms of % (Percentage) Less than /excess over/Schedule of rate over the amount put to tender amount as given above. (Both in words & Figures) |Schedule of |
| | Rate |
| |% |
| | excess or |
| | |
| | % less |

Approved for
Total :16(Sixteen) items only

Full signature of the Contractor

| | |
|------------|---|
| 01. | Total No. of Corrections..... |
| 02. | Total No. of Overwritings..... |
| 03. | Total No. of Interpolations..... |
| 04. | E.M.D. Furnished/ EMD Exempted |
| | a) Demand Draft No |
| | b) Amount Rs..... |
| 05. | Copy of Pan Card : furnished/ not furnished |
| 06. | Copy of G.S.T Liciance : furnished/ not furnished |
| 07. | Copy of Contractor's licence : furnished/not furnished |
| 08. | Copy of Experience Certificate : furnished/ not furnished |
| 09. | Total No. of sheets in the Tender Papers : |

Full Signature of Contractor

Block Development Officer
Kolabira