

Tender Inviting Authority :-

Name of work :- **Completion of Building for the District Bar Association Jharsuguda Municipality (RE)**

Contact No.:-

Bidder Name :-

Price Schedule

This BOQ template must not be modified/replaced by the Bidder and the same should be uploaded after filling the relevent columns, elas the Bidder is liable to be rejected for this tender,Bidders are allowed to enter the Bidder name and values only)

Sl. No.	Item Description	Quantity	Unit	Estimate rate		Total Amunt without Taxes
				Figure	words	
1	2	3	4	5	6	7
1	Fly Ash Brick masonry in cement mortar (1:6) in Super-structure with best quality bricks having crushing strenth no less than 75 kg/sq.cm with dimensional tolerance # 2% immersing the bricks in water for not less than 6 hours before use(the bricks shall be well burnt, free from cracks, well shaped,uniform in size and shall produce a clear ringing sound when struck) includes moulding, chamfering, corbelling etc. complete as per drawing, design and specification, watering and curing for seven days incl. cost , conveyance, royalty and taxes of all materials, labour T&P etc. complete as directed by E.I.C.					
	In Superstruture (1st. floor)	12.69	Cum.	5642 51	Five thousand six hundred fourty two & fifty one paise only	71603.45
2	R.C.C work M-25 grade concrete having minium compressive strength 200Kg/cm2 in 15cm cubes at 28days after mixing and test conducted in accordance with IS 456 and IS 516 using 20mm &10mm size black hard crusher broken granite chips incl. hoisting lowering laying and compacting concrete by using vibrator with watering and curing for 28days centring shuttering and finishing the exposed surface smooth providing groves or beds wherever necessary including cost , conveyance royalties and all taxes and cost of all materials and labour with T&P required for the work etc. complete as directed by E.I.C					
	(i) Roof Slab & Chajjah (First floor)	3.72	Cum.	15373.81	Fifteen thousand three hundred seventy three & eighty one paise only	57190.57
3	Straightening, cutting,bending and binding, welding and jointing (if necessary) coiled/bentup MS Rod/HYSD rods etc.including hoisting,placing in position, tying the grills binding with 18 to 20 gauge binding wires required for R.C.C works, cost of all labours T&P etc. as required for the work complete as directed by E.I.C including cost of rod.					

	(i) 1st. Floor	4.00	Qtl.	9352.07	Nine thousand three hundred fifty two & seven paise only	37408.28
4	Providing 25mm thick grading concrete in terrace (1:2:2) admixed with waterproofing compound of approved quality to be mixed with specified ratio including watering, curing, including cost of all materials, conveyance, loading and unloading, all taxes and royalties, T&P etc. complete as required for the finished item of work as directed by E.I.C.	348.08	Sqm.	383.42	Three hundred eighty three & forty two paise only	133460.83
5	12 mm (½") thick cement plaster (1:6) with neat cement punning in finished smooth brick walls and skirting after racking out the joints including watering and curing complete with cost conveyance royalties and all taxes of all materials and cost of all labour with T & P required for the work etc. complete.					
	(i) GroundFloor	87.62	Sqm.	162.36	one hundred sixty two & thirty six paise only	14225.98
	(i) 1st. Floor	180.11	Sqm.	169.24	one hundred sixty nine & twenty four paise only	30481.82
6	Providing 16 mm thick cement plaster to the inside surface of brick masonry wall with cement mortar (1:6) including racking out of joints, scraping and cleaning the surface with finishing the plaster surface smooth using wooden floats only to the proper plumbs and materials & all taxes, royalties, watering & curing etc. complete as directed by E.I.C					
	(i) Ground floor	31.04	Sqm.	230.00	Two hundred thirty only	7139.20
	(ii) 1st. Floor	61.32	Sqm.	237.00	Two hundred thirty seven only	14532.84
7	Supplying, fitting and fixing Vetrified tile in floors of size 600 mm x 600 mm of approved make confirming to IS 13755 laid on 20 mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all matrials. Labour T&P etc. required for the work all complete as per direction of the Enginreer- in- Charge (For New work only)					
	(i) Ground floor	39.16	Sqm.	988.40	Nine hundred eighty eight & forty paise	38705.74
	(ii) 1st. Floor	308.16	Sqm.	1081.55	One thousand eighty one & fifty five paise only	333290.45
8	Fixing Floor tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 jointed with neat cement slurry mixed with pigment to match the shades of tiles including rubbing & polishing complete including cost of tiles					
	(i) Floor Tiles	6.30	Sqm.	903.24	Nine hundred three & twenty four paise only	5690.41

	(ii) Kota tiles	67.18	Sqm.	860.82	Eight hundred Sixty & eighty two paise only	57829.89
9	Fixing Wall tiles in dadoes skirting and risers of steps on 12mm thick bed of cement mortar 1:3 jointed with neat cement slurry mixed with pigment to match the shades of tiles including rubbing & polishing complete including cost of tiles					
	(ii) 1st. Floor	55.37	Sqm.	867.88	Eight hundred sixty seven & eighty eight paise only	48054.52
10	Finishing wall surface of walls with Cement based wall putty (Water based) of approved make and finised smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc. complete.					
	(i) Ground floor	118.67	Sqm.	73.32	Seventy three & thirty two paise only	8700.88
	(ii) 1st. Floor	1219.48	Sqm.	74.60	Seventy four & sixty paise only	90973.21
11	Priming one coat of wall primer including cost of paint etc. per sqm.					
	(i) Ground floor	118.67	Sqm.	28.92	Twenty eight & ninty two paise only	3431.94
	(ii) 1st. Floor	1571.86	Sqm.	29.49	Twenty nine & fourty nine paise only	46354.15
12	Finishing walls with water-proofing weather coat paints of approved shade on new work 2 coats to give an even shade including cost of cement paint with conveyance, sundries T&P etc required for the work complete as directed by E.I.C					
	(i) 1st. Floor	388.34	Sqm.	87.81	Eighty seven & Eighty one paise only	34100.14
13	Distempering two coats with any approved shade over the interior surface of walls etc complete in all floors as directed by the Engineer-in-Charge over a coat of chalk washing using distemper including cost conveyance of all materials including cost of distemper with all taxes and cost of all labour with T&P required for the work etc complete in all respect .					
	(i) Ground floor	118.67	Sqm.	74.48	Seventy four & fourty eight paise only	8838.54
	(ii) 1st. Floor	1219.48	Sqm.	76.68	Seventy six & sixty eight paise only	93509.73
14	Priming one coats with any approved paint including cost of paints, brush etc. per sqm.	35.00	Sqm.	67.75	Sixty seven & Seventy five paise only	2371.25
15	Painting two coats with paints of approved shade over a base coat of primer of any approved primer in all floors to iron work including sand papering polishing the surface, including cost conveyance royalties and all taxes of all materials along with T & P required for the work including cost of paints etc. complete in all respect	35.00	Sqm.	161.18	one hundred Sixty one & eighteen paise only	5641.30

16	Supplying fitting & fixing MS doors Windows incl all labours T & P etc.	150.00	Kg.	120.00	one hundred twenty only	18000.00
17	Supplying & fitting of Aluminium Flush door	4	No.	7500.00	Seven thousand five hundred only	30000.00
18	Costruction of Display board & site devloipement	1	Nos	6000.00	Six thousand only	6000.00
19	Work Contingency					11975.00
	Total					1209510.12

Say 1209510.00


 Junior Engineer
 Jharsuguda Block


 Assistant Exe. Engineer
 Jharsuguda Block


 Block Development Officer
 Jharsuguda Block

My/ our quoted rate is _____ % (both figure & words) excess over/ less than /equal to above estimated cost.

Signature of the tenderer

Notes:- (1) The contractor should not write any thing except quoting of percentage and in case of any thing else regarding tender rate mentioned, the tender is liable for rejection.

(2) Strike out which are not applicable.


 Block Development Officer
 Jharsuguda

Signature of the tenderer

Total-19 (Nineteen) items only.

No. of Correction
 No. of Overwriting
 No. of Interpolation

Approved for - 19 (Nineteen) Items only.

Signature of Contractor


 Block Development Officer
 Jharsuguda Block