

**CONSTRUCTION OF ADDITIONAL CLASS ROOM AT PANDRI HIGH SCHOOL**  
**BILL OF QUANTITY**

SL NO	ITEM OF WORK	QUANTITY	UNIT	RATE	AMOUNT
1	Earth work excavation in hard soil within Initial lead and initial lift including rough dressing and levelling the foudation bed and depositing the excavted earth away from work site	57.51	Cum	263.80	15,171.00
2	Filling foundation and plinth with well watered and rammed sand including all cost, conveyance and royalty of all materials etc.	39.25	Cum	694.80	27,271.00
3	CC(1:3:6) using 40 mm size CBG mental in foudation including all cost, conveyance, curing and royalty etc complete.	13.15	Cum	6057.10	79,651.00
4	First Class Fly ash bricks in C.M (1:6) in foundation and plinth including cost conveyance & royalty of the materials etc complete	24.78	Cum	5374.50	1,33,180.00
5	First Class Fly ash bricks in C.M (1:4) in Superstructre including cost conveyance & royalty of the materials etc complete	26.00	Cum	5407.90	1,40,605.00
6	RCC work M-20 grade using 20mm and down grade CBG including cost conveyance & royalty of the materials etc complete	0.00		0.00	
	a) Column Base	10.58	Cum	6564.15	69,449.00
	b) Plinth Beam	2.57	Cum	7429.70	19,094.00
	c) For Beam & Column	9.21	Cum	18682.80	1,72,069.00
	d) Lintel Bend	2.57	Sqm	14211.00	36,522.00
	e) Chajja	1.27	Sqm	1216.04	1,544.00
	f) Roof Slab	9.66	Sqm	13729.20	1,32,624.00
7	Supplying , fitting and placeing uncoated HYSD bar reinforcement as per drawing and technical specification including cost conveyance and all taxes of steel and binding wire etc.	28.69	Sqm	9099.60	2,61,049.00
8	Supplying , Fitting and Fixing Steel Angle Iron door and Windows as per approved design and drawing including all cost of materilas and labour etc.	347.90	Kg	90.00	31,311.00
9	6mm thick Cement Plaster in CM (1:4) over RCC with close deep chiping including cost conveyance and roylity of materials curings etc.	60.20	Sqm	208.50	12,552.00

10	16 mm thick C.P. in C.M.(1:6) over brick masonry including watering and curing and finishing including cost, conveyance royalty etc.	121.90	Sqm	269.10	32,803.00
11	12 mm thick C.P. in C.M.(1:6) over brick masonry including watering and curing and finishing including cost, conveyance royalty etc.	91.88	Sqm	186.70	17,154.00
12	20mm thick grading Plaster (1:4) finished smooth over roof slab after cleaning the surface including cost conveyance and roylity of materials curings etc.	75.54	Sqm	292.30	22,080.00
13	Supplying, Fitting and Fixing Vittied tiles in Floors of Size (600x600) mm of Approved make conforming to IS:13755 laid on 20mm thick cement mortar (1:4) (1Cement:4Course sand) and filling joints with white cement of approved quality including cost of all materials.labour T&P etc required for the work all complete as per direction of engineer -in -charge (for new work Only)	56.74	Sqm	1140.50	64,712.00
14	Fixing tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing complete excluding cost of precast tiles.	35.58	Sqm	1713.86	60,979.00
15	Finishing wall surface of walls with Acrylic wall putty (Water based ) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc complete.	146.52	Sqm	89.60	13,128.00
16	Priming with wall cement primer (water bound) of approved shade on new work to give an even shade excluding cost of primer etc complete.	238.40	Sqm	67.20	16,020.00
17	Painting two coats with approved paint on new wood / iron work Sqm.	22.95	Sqm	160.00	3,672.00
18	Finishing outside walls with two coats of weather coat paint of approved shade on new work to give an even shade including cost of paint etc.	91.88	Sqm	73.90	6,790.00
19	Display board				5,000.00
20	Fire fighting arrangement				7,000.00
21	Electrification				30,000.00
22	Black Board				8,000.00
23	shelve				6,000.00
	<b>TOTAL</b>				<b>Rs. 14,25,430.00</b>

  
Assistant Executive Engineer  
Lakhanpur Block

  
AE/JE/GPTA  
Lakhanpur Block

**APPROVED FOR 19 (Nineteen) ITEMS ONLY**

My/our quoted rate is ..... % ( both in figures and words) excess over / less than / equal to the above estimated cost.

**Signature of Tenderer**

  
**Block Development Officer  
Lakhanpur**

**NOTES :-**

1. The contractor should not write anything excepting quoting of percentage and in any case
2. Percentage quoted by the tenderer shall be accurately filled in words and in figures..
3. Strike out which is not applicable. If the tenderer quotes the percentage without
4. Percentage should be quoted up to (one) digit after the decimal point. If the tenderer
5. Rate of all items are inclusive of cost, carriage, royalty, cess and other taxes of materials.

**Tenderer**

No. of corrections.....

No. of Over writings.....

No. of Interpolations.....