

## TENDER SCHEDULE

1	Name of Work	<b>CONST.OF ADDL.CLASS ROOM AT GOVT.UPPER PRIMARY SCHOOL LARIAPALI UNDER POKHARASALE GP</b>
2	Estimated cost	Rs.15,47,000/-
3	Amount Put to Tender	Rs.12,60,221/-
4	Earnest Money Deposit E.M.D. (1%)	Rs.12,602.00
5	Class of Contractor	"C" and "D" Class
6	Cost of tender paper	Rs. 6000/-
7	Period of completion	Six calander months
8	Last Date of Sale of tender paper	01-08-2024 upto 4.00 PM
9	Last Date and Time of receipt of tender paper	01-08-2024 upto 4.00 PM
10	Date and Time of opening of tender paper	02-08-2024 at 11.00 AM

### BOQ

#### CONST.OF ADDL.CLASS ROOM AT GOVT.UPPER PRIMARY SCHOOL LARIAPALI

SL no	Items	Qty	Unit	Rate	Total
1	Earth work excavation in hard soil within Initial lead and initial lift including rough dressing and levelling the foudation bed and depositing the excavted earth away from work site etc.compelte	52.08	Cum	263.80	Rs.13,739.00
2	Filling foundation and plinth with well watered and rammed sand including all cost, conveyance and royalty of all materials etc.	26.03	Cum	694.80	Rs.18,086.00
3	CC(1:3:6) using 40 mm size CBG mental in foudation including all cost,conveyance, curing and royalty etc complete.	11.94	Cum	6057.10	Rs.72,322.00
4	First Class Fly ash bricks in cement mortar (1:6) in foundation and plinth including cost conveyance & royalty of the materials etc complete	24.79	Cum	5374.50	Rs.1,33,234.00
5	First Class Fly ash bricks in C.M (1:4) in Superstructre including cost conveyance & royalty of the materials etc complete	25.09	Cum	5407.90	Rs.1,35,684.00

Signature of Contractor

Block Development Officer, Kolabira

6	RCC work M-20 grade using 20mm and down grade CBG including cost conveyance & royalty of the materials etc complete				
	a) Colounm Base	10.58	Cum	6564.15	Rs.69,449.00
	b) Plinth Beam	2.59	Cum	7429.70	Rs.19,243.00
	c) For Beam & Column	9.26	Cum	18682.80	Rs.1,73,003.00
	d) Lintel Bend	2.59	Sqm	14211.00	Rs.36,806.00
	e) Chajja	1.20	Sqm	1216.04	Rs.1,459.00
	f) Roof Slab	7.67	Sqm	13729.20	Rs.1,05,303.00
7	Supplying , fitting and placeing uncoated HYSD bar reinforcement as per drawing and technical specification including cost conveyance and all taxes of steel and binding wire etc.	27.11	Sqm	9099.60	Rs.2,46,708.00
8	Supplying , Fitting and Fixing Steel Angle Iron door and Windows as per approved design and drawing including all cost of materilas and labour etc.	305.55	Kg	90.00	Rs.27,500.00
9	6mm thick Cement Plaster in CM (1:4) over RCC with close deep chiping including cost conveyance and roylity of materials curings etc.	60.20	Sqm	208.50	Rs.12,552.00
10	16 mm thick C.P. in C.M.(1:6) over brick masonry including watering and curing and finishing including cost, conveyance royalty etc.	116.57	Sqm	269.10	Rs.31,369.00
11	12 mm thick C.P. in C.M.(1:6) over brick masonry including watering and curing and finishing including cost, conveyance royalty etc.	85.81	Sqm	186.70	Rs.16,021.00
12	20mm thick grading Plaster (1:4) finished smooth over roof slab after cleaning the surface including cost conveyance and roylity of materials curings etc.	75.56	Sqm	292.30	Rs.22,086.00

Signature of Contractor

Block Development Officer, Kolabira

13	Supplying, Fitting and Fixing Vitrified tiles in Floors of Size (600x600) mm of Approved make conforming to IS:13755 laid on 20mm thick cement mortar (1:4) (1Cement:4Course sand) and filling joints with white cement of approved quality including cost of all materials, labour T&P etc required for the work all complete as per direction of engineer -in -charge (for new work Only)	56.75	Sqm	1140.50	Rs.64,723.00
14	Fixing tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing complete excluding cost of precast tiles.	8.36	Sqm	1713.86	Rs.14,328.00
15	Finishing wall surface of walls with Acrylic wall putty (Water based ) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc complete.	168.41	Sqm	89.60	Rs.15,090.00
16	Priming with wall cement primer (water bound) of approved shade on new work to give an even shade excluding cost of primer etc complete.	254.22	Sqm	67.20	Rs.17,084.00
17	Painting two coats with approved paint on new wood / iron work Sqm.	19.32	Sqm	160.00	Rs.3,091.00
18	Finishing outside walls with two coats of weather coat paint of approved shade on new work to give an even shade including cost of paint etc.	85.81	Sqm	73.90	Rs.6,341.00
19	Display Board				Rs.5,000.00
<b>Total</b>					<b>Rs.12,60,221.00</b>
Total 19 ( Ninteen) Items					<b>Total Rs.12,60,221.00</b>
<b>( Rupees Twelve Lakh Sixty Thousand Two Hundred Twenty One ) only</b>					
<b>G.S.T 18% will be paid extra</b>					

Signature of Contractor

Block Development Officer, Kolabira

Rate to be Quoted in terms of % (Percentage) Less than /excess over/Schedule of rate over the amount put to tender amount as given above. (Both in words & Figures)	.....Schedule of
	Rate
	.....%
	excess or
	.....%
	less

Approved for  
Total :19 ( Ninteen ) items only

Full signature of the Contractor

1	Total No. of Corrections.....
2	Total No. of Overwritings.....
3	Total No. of Interpolations.....
4	E.M.D. Furnished/ EMD Exempted
	a) Demand Draft No
	b) Amount Rs.....
5	Copy of Pan Card : furnished/ not furnished
6	Copy of G.S.T Liciance : furnished/ not furnished
7	Copy of Contractor's licence : furnished/not furnished
8	Copy of Experiace Certificate :furnished/ not furnished
9	Total No. of sheets in the Tender Papers : .....

Signature of Contractor

Block Development Officer, Kolabira