

**ZILLA PARISHAD
JHARSUGUDA**



**PR & DW DEPARTMENT, ODISHA
BID DOCUMENT**

Name of the Work	:	Improvement and Renovation of Katatikra kata at Kantatikra Village of Kudopali Village
Name of the Block	:	Jharsuguda
Name of the District	:	Jharsuguda
Estimated Cost	:	Rs 49,65,000.00
Tender Value	:	Rs 42,07,116.00

Signature of The Tenderer

Signature of the BDO

Tender Schdule

Tender Inviting Authority : BLOCK DEVELOPMENT OFFICER, JHARSUGUDA						
Name of work :- Improvement and Renovation of Katatikra kata at Kantatikra Village of Kudopali Village						
Tender Call Notice No : of 2023-23						
Name of of the Bidder, Mobile No. and Address :-						
SCHEDULE OF WORK						
Sl. No	Item Description	Quantity	Unit	Estimate rate		Total Amunt without Taxes
				Figure	Words	
1	2	3	4	5	6	7
1	Excavation, loading and carriage by mechanical means all kinds of soil, including stoney earth, gravel and moorum etc interspread with boulders upto 1/2 cum size with all lifts and delifts including trimming of slopes and bed to design section and depositing the excavated materials away from work site as per the specification and as directed by the Engineer-in -charge within an initial lead of 1 km from the place of excavation complete.	13097.00	Cum	127.04	Rupees One Hundred Twenty Seven And Paise Four Only	1663842.88
2	Earth work in excavation of foundation trenches in all kinds of soil including moorum, stoney earth and earth mixed with boulders except sheet rocks and boulders requiring blasting including dressing and leveling the bed upto the required depth and depositing the excavated materials with all leads and lifts T & P shoring & shuttering if required etc. complete.	174.42	Cum	210.97	Rupees Two Hundred Ten And Paise Ninety Seven Only	36797.39
3	Supplying filling in foundation and plinth with sand including watering ramming, cost, conveyance, royalties and all taxes of materials and cost of labour with T & P required for the work etc. complete (measurement will be taken on finished section only).	42.25	Cum	977.69	Rupees Nine Hundred Seventy Seven And Paise Sixty Nine Only	41307.40
4	Cement concrete (1:3:6) nominal mix in levelling coarse below open foundation of head walls as per drawing and technical specification and all taxes of all materials and cost of all labour with T&P required for all the work complete.	59.38	Cum	5903.67	Rupees Five Thousand Nine Hundred Three And Paise Sixty Seven Only	350559.92
5	Cement concrete (1:4:8) nominal mix in levelling coarse below open foundation of head walls as per drawing and technical specification and all taxes of all materials and cost of all labour with T&P required for all the work complete.	9.29	Cum	5245.57	Rupees Five Thousand Two Hundred Forty Five And Paise Fifty Seven Only	48731.35
6	Cement concrete (1:2:4) by using 12mm sizevc.b.h.g chips of approved quality including all labours T&P and cost, Conveyance of materials, etc. Complete.	7.02	Cum	7412.63	Rupees Seven Thousand Four Hundred Twelve And Paise Sixty Three Only	52036.66
7	Cement concrete M15 grade with crushed granite coarse aggregate of size 20 mm down graded including cost of all materials, machineries and labour and compacting with vibrator and finishing the concrete surface etc. complete.	157.20	Cum	5975.60	Rupees Five Thousand Nine Hundred Seventy Five And Paise Sixty Only	939364.32
8	R.C.C.(M20) by using 20mm & down graded black hard granite crusher broken chips including hoisting & laying etc. cost. Carriage & royalty etc. complete.	5.40	Cum	6355.93	Rupees Six Thousand Three Hundred Fifty Five And Paise Ninety Three Only	34322.02

Signature of The Tenderer

Signature of the BDO


	K. B. Brick masonry in cement mortar (1:6) in Super-structure with best quality bricks having crushing strength from 75 kg/sq.cm to 99 kg/sq.cm immersing the bricks in water for not less than 6 hours before use(the bricks shall be well burnt, free from cracks, well shaped, uniform in size and shall produce a clear ringing sound when struck) includes moulding, chamfering, corbelling etc. complete as per drawing, design and specification, watering and curing for seven days incl. cost, conveyance, royalty and taxes of all materials, labour T&P etc. complete as directed by E.I.C.	7.18	Cum	5118.83	Rupees Five Thousand One Hundred Eighteen And Paise Eighty Three Only	36753.20 ✓
10	Providing 12 mm thick cement plaster to the outside surface of brick masonry wall with cement mortar (1:6) including racking out of joints, scraping and cleaning the surface with finishing the plaster surface smooth using wooden floats only to the proper plumbs and materials & all taxes, royalties, watering & curing etc. complete as directed by E.I.C	32.28	Sqm.	161.76	Rupees One Hundred Sixty One And Paise Seventy Six Only	5221.61 ✓
11	Providing 16 mm thick cement plaster to the inside surface of brick masonry wall with cement mortar (1:6) including racking out of joints, scraping and cleaning the surface with finishing the plaster surface smooth using wooden floats only to the proper plumbs and materials & all taxes, royalties, watering & curing etc. complete as directed by E.I.C	24.34	Sqm.	229.28	Rupees Two Hundred Twenty Nine And Paise Twenty Eight Only	5580.68 ✓
12	2.5 cm.(1")ave. thick A.S. Flooring with cement concrete of prop (1:2:4) with black hard crusher broken granite chips including rounding of corners watering and curing with cost conveyance royalties and all taxes of all materials and cost of all labour with T & P required for the work etc. complete.	4.04	Sqm.	358.34	Rupees Three Hundred Fifty Eight And Paise Thirty Four Only	1447.69 ✓
13	Rigid and smooth Centering and shuttering for R.C.C.Works and dismantling then after casting including cost of all materials complete.					
	i) Mass Concrete	436.02	Per Sqm	234.00	Rupees Two Hundred Thirty Four Only	102028.68 ✓
	ii) Slab	26.28	Per Sqm	670.21	Rupees Six Hundred Seventy And Paise Twenty One Only	17613.12 ✓
	iii) wall & fine	123.84	Per Sqm	891.15	Rupees Eight Hundred Ninety One And Paise Fifteen Only	110360.02 ✓
14	Straightening, cutting, bending and binding, welding and jointing (if necessary) coiled/bent up MS Rod/HYSD rods etc. including hoisting, placing in position, tying the grills binding with 18 to 20 gauge binding wires required for R.C.C works, cost of all labours T&P etc. as required for the work complete as directed by E.I.C including cost of rod.	13.00	Qtl	7787.51	Rupees Seven Thousand Seven Hundred Eighty Seven And Paise Fifty One Only	101237.63 ✓
15	Provision for Fine dressing and turfing the slopes of the embankment with compact dub. grass with all lifts & lead of 1 km as per the direction of engineer-in-charge.	3490.00	Sqm.	22.26	Rupees Twenty Two And Paise Twenty Six Only	77687.40 ✓
16	Rough stone dry packing in embankment with other than granite stones (15cm to 30cm) etc. complete	117.00	Cum.	1962.86	Rupees One Thousand Nine Hundred Sixty Two And Paise Eighty Six Only	229654.62 ✓


Signature of The Tenderer


Signature of the BDO

17	Collecting conveying and stacking good quality of latrite moorum on road side in regular box heap of size 1.5mx 1.5 x 0.5 to be measured as 1cum. e ⁺ complete.	93.00	Cum.	468.99	Rupees Four Hundred Sixty Eight And Paise Ninety Nine Only	43616.07 ✓
18	Conveying for stack and spreading moorum on road surface without watering without rolling including all cost etc complete	93.00	Cum.	126.87	Rupees One Hundred Twenty Six And Paise Eighty Seven Only	11798.91 ✓
19	Supplying, Fitting, fixing and installation of solar light (LED-15watt, Solar Panel-75 watt, Battery-18Ah, GI Pole-6mtr. and 3inch)	6	Nos	27000.00	Rupees Twenty Seven Thousand Only	162000.00 ✓
20	Precast Concrete chair	10	Nos	5000.00	Rupees Five Thousand Only	50000.00 ✓
21	Dewatering, Photograph, Bus cutting	1	Nos	37000.00	Rupees Thirty Seven Thousand Only	37000.00 ✓
22	Costruction of Display board	1	Nos	6500.00	Rupees Six Thousand Five Hundred Only	6500.00 ✓
23	Work Contigency 1%					41655.00 ✓
				Total		4207116.57
Twenty Three (23) nos. only				Say Rs		4207116.00

Rupees Forty Two Lakh(s) Seven Thousand One Hundred Sixteen Only


Assistant Engineer
Jharsuguda Block


Assistant Executive Engineer
Jharsuguda Block


Block Development Officer
Jharsuguda Block

My/ our quoted rate is _____ % (both figure & words) excess over/ less than / equal to above estimated cost.

Signature of the tenderer

- 1 The contractor should not write any thing except quoting of percentage and in case of any thing else regarding tender.
- 2 Strike out which are not applicable.
- 3 Percentage quoted by the contractor shall be accurately filled in figures and words so there is no discrepancy.
- 4 If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
- 5 The percentage quoted in the tender without mentioning excess or less will be treated as excess.
- 6 The contractor will write percentage excess or less upto one decimal point only. If he writes the percentage excess or less upto two or more decimal point shall only be considered.

APPROVED

For 23(Twenty Three) item Only

Signature of the tenderer

Total-23 (Twenty Three) items only.

No. of
No. of Overwriting
No. of Interpolation

Approved for - 23(Twenty Three) Items only.

Block Development Officer
Jharsuguda

Signature of Contractor

Block Development Officer
Jharsuguda

Signature of The Tenderer

Signature of the BDO