


# AUTHORITY INVITING TENDER:- BLOCK DEVELOPMENT OFFICER, LAIKERA

## BOQ FOR THE WORK :-CONSTRUCTION OF ADDL CLASS ROOM AT GOVT. PRY. SCHOOL, KHAMARDIHI OF TILEIMAL GP IN LAIKERA BLOCK UNDER THE SCHEME SCHOOL & MASS EDUCATION DEPARTMENT FOR THE YEAR 2024-25

Item no	Item of Work	Qty	Unit	Rate in Figure	Rate in words	Amount
1	Earthwork in excavation in hard soil within 50m initial lead & 1.5m initial lift including rough dressing & breaking clods to maximum 5cm to 7cm & laying in layers not exceeding 0.3m in depth	49.320	Cum	Rs. 267.03	Rupees Two Hundred Sixty Seven And Paise Three Only.	Rs. 13,170.00
2	Filling F&P with sand well watered and rammed including cost conveyance and royalty etc.	48.070	Cum	Rs. 685.97	Rupees Six Hundred Eighty Five And Paise Ninety Seven Only.	Rs. 32,975.00
3	Plain cement concrete (1:3:6) with 4cm CBHG metal including cost conveyance and royalty in foundation	14.030	Cum	Rs. 5,946.24	Rupees Five Thousand Nine Hundred Fourty Six And Paise Twenty Four Only.	Rs. 83,426.00
4	Brick work with Fly ash Bricks 25cm x 12cm x 8cm size in cement mortar (1:6) in Foundation and Plinth	11.500	Cum	Rs. 5,605.92	Rupees Five Thousand Six Hundred Five And Paise Ninety Two Only.	Rs. 64,468.00
5	Supplying fitting & placing uncoated HYSD bar reinforcement including cost of all materials and labour etc. complete	25.920	Qtl	Rs. 8,990.73	Rupees Eight Thousand Nine Hundred Ninety And Paise Seventy Three Only.	Rs. 2,33,071.00
6	RCC work of M 20 grade with 20 mm and down graded black hard Crusher broken granite stone chips including hosting ,laying & cost of C&S complete.					
a)	Column Base	9.110	Cum	Rs. 6,453.80	Rupees Six Thousand Four Hundred Fifty Three And Paise Eighty Only.	Rs. 58,794.00
b)	Column upto Plinth	0.930	Cum	Rs. 14,233.61	Rupees Fourteen Thousand Two Hundred Thirty Three And Paise Sixty One Only.	Rs. 13,237.00
c)	Plinth Beam	2.770	Cum	Rs. 7,316.27	Rupees Seven Thousand Three Hundred Sixteen And Paise Twenty Seven Only.	Rs. 20,266.00
7	RCC work of M 20 grade with 20 mm and down graded black hard Crusher broken granite stone chips including hosting ,laying & cost of C&S complete.					
a)	Column	2.750	Cum	Rs. 14,233.61	Rupees Fourteen Thousand Two Hundred Thirty Three And Paise Sixty One Only.	Rs. 39,142.00
b)	Lintel band	1.570	Cum	Rs. 13,949.51	Rupees Thirteen Thousand Nine Hundred Fourty Nine And Paise Fifty One Only.	Rs. 21,901.00
c)	Chajja	0.760	Cum	Rs. 16,505.06	Rupees Sixteen Thousand Five Hundred Five And Paise Six Only.	Rs. 12,544.00
d)	Roof Beam	2.130	Cum	Rs. 14,233.61	Rupees Fourteen Thousand Two Hundred Thirty Three And Paise Sixty One Only.	Rs. 30,318.00
e)	Roof Slab	9.440	Cum	Rs. 13,901.79	Rupees Thirteen Thousand Nine Hundred One And Paise Seventy Nine Only.	Rs. 1,31,233.00
8	Fly ash brick masonry in CM1:6) in S/S, using standard size and quality of bricks including cost, conveyance, royalty and all taxes of material and labour etc complete.	21.880	Cum	Rs. 5,643.87	Rupees Five Thousand Six Hundred Fourty Three And Paise Eighty Seven Only.	Rs. 1,23,488.00
9	20 mm thick (1:4) over roof slab as grading plaster including cost, conveyance, watering, curing, royalty and cost of all materials and labour etc. complete.	74.470	Sqm	Rs. 262.31	Rupees Two Hundred Sixty Two And Paise Thirty One Only.	Rs. 19,534.00
10	16mm thick C.P. (1:6) over inside brick wall surface including cost conveyance and royalty of materials complete.	107.420	Sqm	Rs. 273.46	Rupees Two Hundred Seventy Three And Paise Fourty Six Only.	Rs. 29,375.00
11	12mm thick C.P. (1:6) over out side brick wall surface including cost conveyance and royalty of materials complete.	130.980	Sqm	Rs. 190.68	Rupees One Hundred Ninety And Paise Sixty Eight Only.	Rs. 24,975.00
12	6 mm thick C.P.(1:4) to RCC surfaces finished smooth including closed deep chipping and slurry treatment	79.890	Sqm	Rs. 148.88	Rupees One Hundred Fourty Eight And Paise Eighty Eight Only.	Rs. 11,894.00
13	Supplying of fabricated doors and windows with angle iron frames & grills of approved design Including cost, conveyance and taxes of all materials and labour etc.	398.500	Kg	Rs. 94.62	Rupees Ninety Four And Paise Sixty Two Only.	Rs. 37,707.00


  
 16/07/24  
 (JE)


  
**Block Development Officer**  
**LAIKERA**

Item no	Item of Work	Qty	Unit	Rate in Figure	Rate in words	Amount
14	Painting with synthetic paint two coats of approved quality and shade over one coat of primer to iron door & window	23.200	Sqm	Rs. 183.47	Rupees One Hundred Eighty Three And Paise Fourty Seven Only.	Rs. 4,256.00
15	Supplying, fitting and fixing of Vitrified tile in floor on 20 mm thick cement mortar (1:4) and filling joints with white cement	120.400	Sqm	Rs. 1,207.42	Rupees One Thousand Two Hundred Seven And Paise Fourty Two Only.	Rs. 1,45,373.00
16	Fixing Vitrified tiles in dados skirting and risers of steps on 12mm thick CP (1:3) jointed with neat cement slurry mixed with pigments	5.560	Sqm	Rs. 1,334.87	Rupees One Thousand Three Hundred Thirty Four And Paise Eighty Seven Only.	Rs. 7,422.00
17	Finishing wall surface with Acrylic wall putty (water based) of approved make and finish smooth and even surface to receive painting including cost of all materials labour T&P etc complete.	187.310	Sqm	Rs. 90.26	Rupees Ninety And Paise Twenty Six Only.	Rs. 16,906.00
18	Wall Priming one coat with any approved primer on new plastered surface of with any approved primer including cost of primer	318.290	Sqm	Rs. 80.28	Rupees Eighty And Paise Twenty Eight Only.	Rs. 25,553.00
19	Painting 2 coats to wall surface with plastic emulsion paint of approved quality	187.310	Sqm	Rs. 106.22	Rupees One Hundred Six And Paise Twenty Two Only.	Rs. 19,897.00
20	Painting 2 coats to walls surfaces with weather coat of approved shade including all cost, conveyance & royalty etc complete as per direction of the Engineer-in-charge.	130.980	Sqm	Rs. 99.89	Rupees Ninety Nine And Paise Eighty Nine Only.	Rs. 13,084.00
21	Provision for Display Board					Rs. 3,000.00
22	Provision for Fire fighting arrangement					Rs. 6,000.00
23	Provision for Ramp Handrail					Rs. 7,000.00
24	Provision for Black Board, TLM Corner & BALA Activities					Rs. 20,000.00
<b>Total</b>						Rs. 12,70,009.00
25	Add Labour Cess @ 1%					Rs. 12,700.00
<b>TOTAL</b>						Rs. 12,82,709.00

(Rupees Twelve Lakh Eighty Two Thousand Seven Hundred Nine ) Only.

  
 16/07/24  
 Junior Engineer  
 Laikera Block

  
 Asst Executive Engineer  
 Laikera Block  
 18/7/24

  
 18/7/24  
 Block Development Officer  
 Laikera  
 LAIKERA

My/ our quoted rate is \_\_\_\_\_ % (both figure & words) excess over/ less than /equal to above estimated cost.

**Signature of the tenderer**

Notes:- (1) The contractor should not write any thing except quoting of percentage and in case of any thing else regarding tender rate  
 (2) Strike out which are not applicable.

**Signature of the tenderer**

**Block Development Officer  
Laikera**

Total-25(Twenty Five)items only.  
 No. of Correction  
 No. of Overwriting  
 No of Interpolation

**Approved for 25 (Twenty Five) Items only.**

**Signature of Contractor**

**Block Development Officer,  
Laikera**