

TENDER SCHEDULE

Tender Inviting Authority :-

Name of work :- Construction of RCC Bridge at Kanhei Nallah at Pudamam

Contact No.:-

Bidder Name :-

Price Schedule						
This BOQ template must not be modified/replaced by the Bidder and the same should be uploaded after filling the relevant columns, else the Bidder is liable to be rejected for this tender, Bidders are allowed to enter the Bidder name and values only)						
Sl. No.	Item Description	Quantity	Unit	Estimate rate		Total Amount without Taxes
				Figure	words	
1	2	3	4	5	6	7
1	Earth work in excavation of foundation trenches in all kinds of soil including moorum, stoney earth and earth mixed with boulders except sheet rocks and boulders requiring blasting including dressing and leveling the bed upto the required depth and depositing the excavated materials with all leads and lifts T & P shoring & shuttering if required etc.	232.91	Cum.	270.90	Two hundred seventy & Ninty paise only	63095.32
2	Supplying filling in foundation and plinth with sand including watering ramming, cost, conveyance, royalties and all taxes of materials and cost of labour with T & P required for the work etc. complete (measurement will be taken on finished	17.08	Cum.	903.56	Nine hundred three & fifty six paise only	15432.80
3	Cement concrete (1:3:6) in foundation and floor i.e. below the base course of terrazzo flooring using 4 cm. (1½") size black hard hand broken granite stone metals of approved quality from approved quarry including lowering laying concrete watering and curing etc. complete to required level laid in layers not exceeding 0' -6"thick including cost, conveyance, royalties and all taxes of all materials and cost of all labour with T & P required for the	16.25	Cum.	6289.63	Six thousand two hundred eighty nine & Sixty three paise only	102206.49
4	Cement Concrete(1:2:4)with 12mm size C.B.H.G.Chips including cost. Carriage & royalty etc. complete.	159.70	Cum.	7861.64	Seven thousand eight hundred sixty one & sixty four paise only	1255503.91
5	2.5 C.m. D.P.C with cement concrete (1:2:4) using 12 mm. size hard broken granite chips	23.20	Sqm.	384.74	three hundred eighty four & seventy four paise only	8925.97

6	R.C.C work M-25 grade concrete having minium compressive strength 200Kg/cm2 in 15cm cubes at 28days after mixing and test conducted in accordance with IS 456 and IS 516 using 20mm & 10mm size black hard crusher broken granite chips incl. hoisting lowering laying and compacting concrete by using vibrator with watering and curing for 28days centring shuttering and finishing the exposed surface smooth providing groves or beds wherever necessary including cost , conveyance royalties and all taxes and cost of all materials and	129.05	Cum.	6773.42	Six thousand seven hundred seventy three & fourty two paise only	874109.85
7	Straightening, cutting, bending and binding, welding and jointing (if necessary) coiled/bent up MS Rod/HYSD rods etc. including hoisting, placing in position, tying the grills binding with 18 to 20 gauge binding wires required for R.C.C works, cost of all labours T&P etc. as required for the work complete as directed by E.I.C including cost of rod.	129.00	Qtl.	8694.27	Eight thousand eighty six hundred Ninety four & twnty seven paise only	1121560.83
8	Rigid and smooth Centering and shuttering for R.C.C. Works and dismantling then after casting including cost of all materials complete.					
	i) Mass Concrete	552.99	Sqm.	249.07	Two hundred fourty nine & seven paise only	137733.22
	ii) Slab	37.95	Sqm.	755.00	Seven hundred fifty five only	28652.25
9	6mm.thick Cement Plaster(1:4)to R.C.C.surface finished smooth including closed deep chipping and slurry treatment including cost, carriage & royalty etc. complete.	386.08	Sqm.	184.10	One hundred eighty four & ten paise only	71077.33
10	White washing 2 coats etc. per Sqm	386.08	Sqm.	53.61	fifty three & sixty one paise only	20697.75
11	Filling in foundation and plinth with excavated materials including watering and ramming as directed by EIC	370.00	Cum.	180.60	one hundred eighty & sixty paise only	66822.00
12	Collecting, Conveying , Stacking Moorum on road side excluding Watering & Rolling Cost of Moorum	52.50	Cum.	399.48	Three hundred ninty nine & fourty eight paise only	20972.70
13	Labour for laying moorum in sub-base in layers not exceeding 100mm watering and compaction to required density in OMC with PRR finished smooth etc. per Cum.(labour only)	52.50	Cum.	466.87	Four hundred sixty six & eighty seven paise only	24510.68
14	Cleaning grass and removal of rubbish up to a distane of 50 meters outside the periphery of the area	0.45	Hectare	27416.05	twenty seven thousand four hundred sixteen & five paise only	12337.22
15	Fine dressing of earthwork in ordinary soil in road formation accoding to the direction of the department including cutting or filling earth upto 0.15 m depth of surface	150.00	Sqm.	5.35	Five & thirty five paise only	802.50

