



## PANCHAYAT SAMITI OFFICE, KOLABIRA

Dist : Jharsuguda,( Odisha ) Pin : 768213, P.h No: 06640-285110, E-mail: [ori-kolabira@nic.in](mailto:ori-kolabira@nic.in)

No.....560..... / Date...21-02-2025

### ADDENDUM

Please refer to tender call Notice No.540 Date.19.02.2025 regarding Construction of GPLF Building in Kolabira & Samasingha GP Tender Schedule of "CONSTRUCTION OF GPLF BUILDING MARKET COMPLEX AT SAMASINGHA UNDER SAMASINGHA GP" is added.

  
Block Development Officer  
Kolabira

Memo No. 561 / Date. 21-02-2025

Copy to Office Notice Board/Tender File concerned.

  
Block Development Officer  
Kolabira


Memo No. 562 / Date. 21-02-2025

Copy to the Collector & District Magistrate, Jharsuguda / CDO-Cum-EO, Zilla Parishad, Jharsuguda for information and necessary action.

  
Block Development Officer  
Kolabira


Memo No. 563 / Date. 21-02-2025

Copy of Tender Notice & Tender documents submitted to DeGM, Jharsuguda with a request to upload in the District Website [www.jharsuguda.odisha.gov.in](http://www.jharsuguda.odisha.gov.in) for wide publicity.

  
Block Development Officer  
Kolabira

## TENDER SCHEDULE

1	Name of Work	<b>CONSTRUCTION OF GPLF BUILDING WITH MARKET COMPLEX AT SAMASINGHA UNDER SAMASINGHA GP</b>			
2	Estimated cost	Rs.30,00,000/-			
3	Amount Put to Tender	Rs.21,60,611/-			
4	Earnest Money Deposit E.M.D. (1% )	Rs 21606/-			
5	Class of Contractor	"B" and " C" Class			
6	Cost of tender paper	Rs. 6000/-			
7	Period of completion	Six Celender months			
8	Last Date of Sale of tender paper	07-03-2025 upto 4.00 PM			
9	Last Date and Time of receipt of tender paper	07-03-2025 upto 4.00 PM			
10	Date and Time of opening of tender paper	11-03-2025 at 11.00 AM			
<b>BOQ</b>					
<b>CONSTRUCTION OF GPLF BUILDING WITH MARKET COMPLEX AT SAMASINGHA UNDER</b>					
SL no	Items	Qty	Unit	Rate	Total
1	Earth work excavation in hard soil within Initial lead and initial lift including rough dressing and levelling the foudation bed and depositing the excavted earth away from work site etc.compelte	65.50	Cum	269.70	Rs.17,664.00
2	Filling foundation and plinth with well watered and rammed sand including all cost, conveyance and royalty of all materials etc.	23.35	Cum	694.80	Rs.16,221.00
3	CC(1:3:6) using 40 mm size CBG metal in foudation including all cost,conveyance, curing and royalty etc complete.	16.74	Cum	6057.10	Rs.1,01,383.00
4	Fly ash bricks in C.M (1:6) in F & P including cost conveyance & royalty of the materials etc complete	12.43	Cum	5374.00	Rs.66,787.00
5	Fly ash bricks in C.M (1:6) in Superstructure including cost conveyance & royalty of the materials etc complete	31.97	Cum	5407.50	Rs.1,72,890.00
6	Fly ash bricks in C.M (1:4) in Superstructure including cost conveyance & royalty of the materials etc complete	2.75	Cum	5582.80	Rs.15,342.00
7	RCC work M-20 grade using 20mm and down grade CBG including cost conveyance & royalty of the materials etc complete				
	a) Column Base	11.93	Cum	6564.15	Rs.78,341.00
	b) Plinth Beam	4.23	Cum	7429.70	Rs.31,395.00
	c) Column & Beam	16.59	Cum	15682.80	Rs.2,60,148.00
	d) Lintel	2.57	Cum	14211.00	Rs.36,586.00
	e) Chajja/ Roof Slab	16.16	Cum	13729.20	Rs.2,21,867.00
8	Supplying , fitting and placeing uncoated HYSD bar reinforcement as per drawing and technical specification including cost conveyance and all taxes of steel and binding wire etc.	51.82	Qntl	9099.60	Rs.4,71,500.00
9	2.5 cm thick grading concrete (1:2:2) on roof slab with 4.7 mm size hard granite chips including all ,cost.conveyance,roylity etc.complete	123.74	Cum	383.60	Rs.47,467.00



10	6mm thick cement plaster in C.M (1:4) for ceiling plaster including deep chipping etc.	130.02	Sqm	208.50	Rs.27,108.00
11	16 mm thick C.P. in C.M.(1:6) over brick masonry including watering and curing and finishing including cost, conveyance royalty etc.	304.97	Sqm	269.10	Rs.82,067.00
12	12 mm thick C.P. in C.M.(1:6) over brick masonry including watering and curing and finishing including cost, conveyance royalty etc.	367.53	Sqm	186.70	Rs.68,617.00
13	Supplying fitting & fixing of MS Door & Window including all cost of materials & Labour Charges etc.	1268.50	Kg	90.00	Rs.1,14,165.00
14	Supplying fitting & fixing of UPVC Door Including all cost of materials & Labour Charges etc.	2.00	Sqm	5500.00	Rs.11,000.00
15	Supplying,Fitting and Fixing Vetrified tiles in Dados of Size (600x600) mm of Approved make conforming to IS:13755 laid on 20mm thick cement mortar (1:3) (1Cement:3Course sand) and filling joints with white cement of approved quality including cost of all materials.	12.99	Sqm	1713.86	Rs.22,270.00
16	Supplying,Fitting and Fixing Vetrified tiles in Floors of Size (600x600) mm of Approved make conforming to IS:13755 laid on 20mm thick cement mortar (1:4) (1Cement:4Course sand) and filling joints with white cement of approved quality including cost of all materials.	95.36	Sqm	1140.50	Rs.1,08,754.00
17	30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755 slurry mixed with pigments to matche shade of the tiles including polishing complete as per direction of Engineer-in-charge.	10.83	Sqm	1038.04	Rs.11,244.00
18	20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753 and filling joints with white cement of approved quality including cost of all materials.etc	30.78	Sqm	854.90	Rs.26,312.00
19	Two coats of enamel painting over one coat of primer to doors and windows etc.	69.68	Sqm	191.70	Rs.13,357.00
20	Priming with wall cement primer (Oil bound) of approved shade on new work to give an even shade including cost of primer etc complete.	758.74	Sqm	76.20	Rs.57,816.00
21	Wall painting with two coats weather coat paint of approved shade on new wrk to give an even shade including cost of paint.	367.53	Sqm	95.70	Rs.35,172.00
22	Wall painting two coats on new work with plastic emulsion paint of approved shade of approved make.	391.21	Sqm	102.60	Rs.40,138.00
23	Display Board				Rs.5,000.00
				<b>Total</b>	<b>Rs.21,60,611.00</b>
<b>Total 23 ( Twenty Three) Items</b>				<b>Total</b>	<b>Rs.21,60,611.00</b>
<b>( Rupees Twenty One Lakh Sixty Thousand Six Hundred Eleven ) only</b>					
<b>G.S.T 18% will be paid extra</b>					

<b>Rate to be Quoted in terms of % (Percentage) Less than /excess over/Schedule of rate over the amount put to tender amount as given above. (Both in words &amp; Figures)</b>	<p style="text-align: right;">.....Schedule of</p> <p style="text-align: center;">Rate</p> <hr style="border-top: 1px dotted black;"/> <p style="text-align: center;">% excess</p> <p style="text-align: right;">or</p>
<b>Approved for</b>	
Total :23 ( Twenty Three ) items only	
1	Total No. of Corrections.....
2	Total No. of Overwritings.....
3	Total No. of Interpolations.....
4	E.M.D. Furnished/ EMD Exempted
	a) Demand Draft No
	b) Amount Rs.....
5	Copy of Pan Card : furnished/ not furnished
6	Copy of G.S.T Liciance : furnished/ not furnished
7	Copy of Contractor's licence : furnished/not furnished
8	Copy of Experiance Certificate :furnished/ not furnished
9	Total No. of sheets in the Tender Papers : .....

**Full signature of the Contractor**

