

AUTHORITY INVITING TENDER:- BLOCK DEVELOPMENT OFFICER, LAIKERA

BOQ FOR THE WORK :-CONSTRUCTION OF G.P.L.F. OFFICE BUILDING WITH MARKET COMPLEX AT LAIKERA GP FOR THE YEAR 2024-25

| item no | Item of Work | Qty | Unit | Rate in Figure | Rate in words | Amount |
|---------|---|----------|------|----------------|---|-----------------|
| 1 | Earthwork in excavation in hard soil within 50m initial lead & 1.5m initial lift including rough dressing & breaking clods to maximum 5cm to 7cm & laying in layers not exceeding 0.3m in depth | 91.520 | Cum | Rs. 267.03 | Rupees Two Hundred Sixty Seven And Paise Three Only. | Rs. 24,439.00 |
| 2 | Filling F&P with sand well watered and rammed including cost conveyance and royalty etc. | 46.950 | Cum | Rs. 685.97 | Rupees Six Hundred Eighty Five And Paise Ninety Seven Only. | Rs. 32,205.00 |
| 3 | Plain cement concrete (1:3:6) with 4cm CBHG metal including cost conveyance and royalty in foundation | 22.260 | Cum | Rs. 5,946.24 | Rupees Five Thousand Nine Hundred Forty Six And Paise Twenty Four Only. | Rs. 1,32,361.00 |
| 4 | Brick work with Fly ash Bricks 25cm x 12cm x 8cm size in cement mortar (1:6) in Foundation and Plinth | 39.800 | Cum | Rs. 5,605.92 | Rupees Five Thousand Six Hundred Five And Paise Ninety Two Only. | Rs. 2,23,117.00 |
| 5 | Fly ash brick masonry in CM1:6) in S/S, using standard size and quality of bricks including cost, conveyance, royalty and all taxes of material and labour etc complete. | 37.870 | Cum | Rs. 5,643.87 | Rupees Five Thousand Six Hundred Forty Three And Paise Eighty Seven Only. | Rs. 2,13,707.00 |
| 6 | RCC work of M 20 grade with 20 mm and down graded black hard Crusher broken granite stone chips including hosting, laying & cost of C&S complete. | | | | | |
| a) | Column Foundation | 16.230 | Cum | Rs. 6,453.80 | Rupees Six Thousand Four Hundred Fifty Three And Paise Eighty Only. | Rs. 1,04,745.00 |
| b) | Plinth Beam | 4.380 | Cum | Rs. 7,316.27 | Rupees Seven Thousand Three Hundred Sixteen And Paise Twenty Seven Only. | Rs. 32,045.00 |
| c) | Column & Beam | 15.550 | Cum | Rs. 14,233.61 | Rupees Fourteen Thousand Two Hundred Thirty Three And Paise Sixty One Only. | Rs. 2,21,333.00 |
| d) | Lintel Bend | 2.920 | Cum | Rs. 13,949.51 | Rupees Thirteen Thousand Nine Hundred Forty Nine And Paise Fifty One Only. | Rs. 40,733.00 |
| e) | Chhaja | 0.420 | Cum | Rs. 16,505.06 | Rupees Sixteen Thousand Five Hundred Five And Paise Six Only. | Rs. 6,932.00 |
| f) | Roof Slab & Septic Tank Slab | 16.880 | Cum | Rs. 13,901.78 | Rupees Thirteen Thousand Nine Hundred One And Paise Seventy Nine Only. | Rs. 2,34,662.00 |
| 7 | Supplying fitting & placing uncoated HYSD bar reinforcement including cost of all materials and labour etc. complete | 59.610 | Qtl | Rs. 8,990.73 | Rupees Eight Thousand Nine Hundred Ninety And Paise Seventy Three Only. | Rs. 5,35,919.00 |
| 8 | 6 mm thick C.P.(1:4) to RCC surfaces finished smooth including closed deep chipping and slurry treatment | 140.610 | Sqm | Rs. 148.88 | Rupees One Hundred Fourty Eight And Paise Eighty Eight Only. | Rs. 20,934.00 |
| 9 | 16mm thick C.P. (1:6) over inside brick wall surface including cost conveyance and royalty of materials complete. | 301.290 | Sqm | Rs. 273.46 | Rupees Two Hundred Seventy Three And Paise Fourty Six Only. | Rs. 82,389.00 |
| 10 | 12mm thick C.P. (1:6) over out side brick wall surface including cost conveyance and royalty of materials complete. | 131.040 | Sqm | Rs. 190.68 | Rupees One Hundred Ninety And Paise Sixty Eight Only. | Rs. 24,987.00 |
| 11 | Supplying of fabricated MS doors and windows with angle iron frames & grills of approved design including cost, conveyance and taxes of all materials and labour etc. | 1444.250 | Kg | Rs. 94.62 | Rupees Ninety Four And Paise Sixty Two Only. | Rs. 1,36,657.00 |
| 12 | Fixing Vitrified tiles in dados skirting and risers of steps on 12mm thick CP (1:3) jointed with neat cement slurry mixed with pigments | 10.560 | Sqm | Rs. 1,334.86 | Rupees One Thousand Three Hundred Thirty Four And Paise Eighty Seven Only. | Rs. 14,094.00 |
| 13 | Supplying, fitting and fixing of Vitrified tile in floor on 20 mm thick cement mortar (1:4) and filling joints with white cement | 106.190 | Sqm | Rs. 1,207.42 | Rupees One Thousand Two Hundred Seven And Paise Fourty Two Only. | Rs. 1,28,214.00 |
| 14 | Fixing Ceramic tile in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed.....polishing complete including cost of Ceramic tile | 29.150 | Sqm | Rs. 1,023.83 | Rupees One Thousand Twenty Three And Paise Eighty Three Only. | Rs. 29,847.00 |
| 15 | Fixing chequered tile treads steps and landing on 25mm thick bed of cement mortar (1:1) jointed.....polishing complete including cost of tile | 11.150 | Sqm | Rs. 767.48 | Rupees Seven Hundred Sixty Seven And Paise Fourty Eight Only. | Rs. 8,556.00 |




03/02/25

Junior Engineer

| item no | Item of Work | Qty | Unit | Rate in Figure | Rate in words | Amount |
|---|--|---------|------|----------------|---|-------------------------|
| 16 | Supplying,fitting and Fixing of stainless steel of 304 grade in hard railing using 50mm. Dia of 2mm. Thick circular pipe with balustrade of size 32mm.x32mm.x2mm in 3rows in staire case as per approved design and specification,buffing,polishing etc with cost,conveyance,taxes of all materials.labour,T&P required for the complete in all respect. | 9.140 | Rmt. | Rs. 3,552.81 | Rupees Three Thousand Five Hundred Fifty Two And Paise Eighty One Only. | Rs. 32,487.00 |
| 17 | Painting with synthetic paint two coats of approved quality and shade over one coat of primer to iron door & window | 104.930 | Sqm | Rs. 257.21 | Rupees Two Hundred Fifty Seven And Paise Twenty One Only. | Rs. 26,989.00 |
| 18 | Wall Priming one coat with any approved primer on new plastered surface of with any approved primer including cost of primer | 572.940 | Sqm | Rs. 80.28 | Rupees Eighty And Paise Twenty Eight Only. | Rs. 45,997.00 |
| 19 | Painting 2 coats to walls surfaces with weather coat of approved shade including all cost, conveyance & royalty etc complete as per direction of the Engineer-in-charge. | 131.040 | Sqm | Rs. 99.89 | Rupees Ninety Nine And Paise Eighty Nine Only. | Rs. 13,090.00 |
| 20 | Wall painting two coats with any approved quality of Plastic emulsion paint over a coat of priming on new work to give an even shade including cost of all materials,labour, T&p required for the work complete. | 441.900 | Sqm | Rs. 106.22 | Rupees One Hundred Six And Paise Twenty Two Only. | Rs. 46,940.00 |
| 21 | Transparency Board | 1.000 | Unit | Rs. 5,000.00 | Rupees Five Thousand Only. | Rs. 5,000.00 |
| Total | | | | | | Rs. 24,18,379.00 |
| 22 | Add Labour Cess @ 1% | | | | | Rs. 24,184.00 |
| 23 | Add Work Contingency @ 1% | | | | | Rs. 24,184.00 |
| G. TOTAL | | | | | | Rs. 24,66,747.00 |
| (Rupees Twenty Four Lakh Sixty Six Thousand Seven Hundred Fourty Seven) Only. | | | | | | |


03/02/25
Junior Engineer
Laikera Block


Asst Executive Engineer
Laikera Block 03/02/25


Block Development Officer
Laikera Block

My/ our quoted rate is _____ % (both figure & words) excess over/ less than /equal to _____ above estimated cost.

Signature of the tenderer

- Notes:- (1) The contractor should not write any thing except quoting of percentage and in case of any thing else regarding tender rate mentioned,the tender is liable for rejection.
(2) Strike out which are not applicable.

Signature of the tenderer

**Block Development Officer
Laikera Block**

Total-23(Twenty Three)items only.

No. of Correction

No. of Overwriting

No of interpolation

Approved for 23 (Twenty Three) Items only.

Signature of Contractor

**Block Development Officer,
Laikera Block**