

AUTHORITY INVITING TENDER:- BLOCK DEVELOPMENT OFFICER, LAIKERA

BOQ FOR THE WORK :-RENOVATION & BEAUTIFICATION OF JAMMAL BADA KANTA IN JAMMAL VILLAGE IN JAMMAL GP IN LAIKERA BLOCK UNDER THE SCHEME DMF FOR THE YEAR 2024-25

item no	Item of Work	Qty	Unit	Rate in Figure	Rate in words	Amount
1	Excavation of foundation in all kinds of soil with all leads and lifts and delifts including dressing and leveling the bed to proper slope and level & making it fit for laying concrete & removing the debris clear of work site with all leads and lifts and delifts including dewatering from foundation if necessary etc. complete in all respect as directed by the Engineer-in-charge.	158.600	Cum	Rs. 222.30	Rupees Two Hundred Twenty Two And Paise Thirty Only.	Rs. 35,256.78
2	Filling F&P with sand well watered and rammed including cost conveyance and royalty etc.complete in all respect as directed by the Engineer-in-charge.	37.820	Cum	Rs. 613.00	Rupees Six Hundred Thirteen Only.	Rs. 23,183.66
3	Cement concrete in (1:3:6) using 40mm Crusher broken granite metal of approved quality quarried and free from weathered skins and foreign materials including mixing the materials by use of concrete mixtures and laying concrete and laying concrete in layers not exceeding 0.15 m. in depth to required level require level, curing, finishing etc with all leads lifts and delifts complete in all respect to proper profile and leveling including dewatering if necessary and cost, conveyance and royalty and other taxes etc of materials including hire and running charges of the machineries complete as directed by the Engineer-in-charge.	272.300	Cum	Rs. 5,760.50	Rupees Five Thousand Seven Hundred Sixty And Paise Fifty Only.	Rs. 15,68,587.15
4	Cement concrete in (1:2:4) using 12mm crusher broken granite Chips of approved quality quarried and free from weathered skins and foreign materials including mixing the materials by use of concrete mixtures and laying concrete and laying concrete in layers not exiding 0.15 m. in depth to required level require level, curing, vubrating with vibrators, finishing etc with all leads lifts and delifts complete in all respect to proper profile and leveling including dewatering if necessary and cost, conveyance and royalty and other taxes etc of materials including hire and running charges of the machineries complete as directed by the Engineer-in-charge.	7.310	Cum	Rs. 7,298.00	Rupees Seven Thousand Two Hundred Ninety Eight Only.	Rs. 53,348.38

C. Prasad
03/02/25

item no	Item of Work	Qty	Unit	Rate in Figure	Rate in words	Amount
5	Cement Concrete M20 with 20 mm Size crusher broken granite metal & down graded of approved quality quarried and free from weathered skin including lifting the materials lowering, hoisting and laying the concrete for required level with curing ramming finishing etc. complete in all respect to proper slope and level with cost, conveyance, royalty and other taxes of all materials etc. complete including dewatering as and when necessary as directed by the Engineer-in-Charge.	5.670	Cum	Rs. 6,309.20	Rupees Six Thousand Three Hundred Nine And Paise Twenty Only.	Rs. 35,773.16
6	Straightening ,cutting,bending,binding and tying the grills as per approved design and placing them in position including cost of cost of binding wire 18 to 20 gauge and including cost and conveyance of HYSR rods etc complete as directed by the Engineer-in-charge .	5.670	Qtl	Rs. 8,607.30	Rupees Eight Thousand Six Hundred Seven And Paise Thirty Only.	Rs. 48,803.39
7	Providing and removing rigid smooth centering and shuttering for C.C./R.C.C. lintel work including cost and conveyance of the materials required for the work complete in all respect as directed by the Engineer-in-Charge.	766.080	Sqm	Rs. 235.50	Rupees Two Hundred Thirty Five And Paise Fifty Only.	Rs. 1,80,411.84
8	Fly ash brick of 23cm X 11cm X 8cm having crushing strength not less than 75 kg / cm ² with dimensional tolerance + 2% percent in cement mortar (1:6) in foundation and plinth including cost conveyance & royalty of the materials etc complete as per direction of the Engineer in Charge .	4.970	Cum	Rs. 5,040.90	Rupees Five Thousand Forty And Paise Ninety Only.	Rs. 25,053.27
9	12mm thick C.P. (1:6) for brick work finished smooth after racking out joints to 12 mm deep including watering and curing and finishing including cost conveyance royalty and other taxes of all materials labour T&P materials required for this item complete as directed by the Engineer-in-Charge .	21.600	Sqm	Rs. 164.80	Rupees One Hundred Sixty Four And Paise Eighty Only.	Rs. 3,559.68
10	16mm thick C.P. (1:6) for brick work finished smooth after racking out joints to 12 mm deep including watering and curing and finishing including cost conveyance royalty and other taxes of all materials labour T&P materials required for this item complete as directed by the Engineer-in-Charge .	16.080	Sqm	Rs. 233.00	Rupees Two Hundred Thirty Three Only.	Rs. 3,746.64
11	Painting one coats of Wall Primer with any approved paint including cost of paints,brush etc per sqm	37.680	Sqm	Rs. 66.80	Rupees Sixty Six And Paise Eighty Only.	Rs. 2,517.02
12	Finishing wall with two coat Weather coat of approved shade on new work one coat to give an even shade .	37.680	Sqm	Rs. 82.20	Rupees Eighty Two And Paise Twenty Only.	Rs. 3,097.29

C/psd
03/02/25

item no	Item of Work	Qty	Unit	Rate in Figure	Rate in words	Amount
13	Excavation, Loading, Unloading and carriage by mechanical means of all kinds of soil, including stoney earth, gravel and moorum etc interespred with boulders upto 1/2 cum size with all lifts & delifts including yrimming of slopes and bed to design section and depositing the excavated materials away from working site as per the specification and as directed by Engineer - incharge within initial lead of 3 Km from the excavation complete.	14256.000	Sqm	Rs. 83.60	Rupees Eighty Three And Paise Sixty Only.	Rs. 11,91,801.60
Total						Rs. 31,75,139.86
14	Signboard					Rs. 5,000.00
TOTAL						Rs. 31,80,139.86
(Rupees Thirty One Lakh Eighty Thousand One Hundred Forty) Only.						Rs. 31,80,140.00

C. Prasad
03/02/25
Junior Engineer
Laikera Block

A. M. Chintu
Asst Executive Engineer
Laikera Block 03/02/25

B. S. S. S.
03/02/25
Block Development Officer
Laikera
LAIKERA

My/ our quoted rate is _____ % (both figure & words) excess over/ less than /equal to above estimated cost.

Signature of the tenderer

- Notes:- (1) The contractor should not write any thing except quoting of percentage and in case of any thing else regarding tender rate mentioned, the tender is liable for rejection.
(2) Strike out which are not applicable.

Signature of the tenderer

**Block Development Officer
Laikera**

Total-26(Twenty Six)items only.

No. of Correction

No. of Overwriting

No of interpolation

Approved for 26 (Twenty Six) Items only.

Signature of Contractor

**Block Development Officer,
Laikera**