

**BOQ**

Tender Inviting Authority: BDO, Lakhampur

Name of Work: Const of Addl Class Room at Govt Upper Primary School Singhaipali, Tilla

**PRICE SCHEDULE**

(this BOQ template must be modified/ replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	Quantity	Units	Estimated Rate	Total Amount Without Taxes	Total Amount in Words
1	Earth work in excavation in foundation in all kinds of soil with all leads and lifts including dressing and levelling the bed in layers not exceeding 0.3 m in depth including dewatering if necessary with cost of all labour and T & P work etc. Complete as per direction of Engineer-in-charge					
	Addl Class Room With Hall At Govt Upper Primary schhol, Singhaipali	57.51	cum	263.80	15171.00	
2	Supplying filling in F & P with clean course good river sand including watering, ramming, poking & compacting & cost, conveyance royalties, taxes of all materials, labour, T & P etc. Complete as per direction of Engineer-in-Charge					
	Addl Class Room With Hall At Govt Upper Primary schhol, Singhaipali	39.25	cum	725.10	28460.00	
3	Providing and laying PCC of (1:3:6) with 2.5cm to 4cm size crusher broken hard black granite metal with cost, conveyance, royalties, taxes of all materials, all labour, T & P etc. Complete as per direction of Engineer-in-charge					
	Addl Class Room With Hall At Govt Upper Primary schhol, Singhaipali	13.15	cum	6402.98	84199.00	
4	Providing and laying RCC work in M-20 grade with 20mm and down grade black hard granite crusher broken stone chips of approved quality from quarry with smooth centering and shuttering hoisting and laying in layers including cost. Conveyance, royalty and taxes of aal materials, labour, T & P etc. complete as per direction of the Engineer-in-charge					
A	<b>Column Base footing</b>					
	Addl Class Room With Hall At Govt Upper Primary schhol, Singhaipali	10.58	Cum	6625.05	70093.00	
B	<b>Plinth Bend</b>					
	Addl Class Room With Hall At Patrapali Primary School	2.57	Cum	7490.60	19251.00	
C	<b>Lintel Beam</b>					

	Addl Class Room With Hall At Govt Upper Primary schhol, Singhaipali	2.57	Cum	14271.90	36679.00	
<b>D</b>	<b>Column Above Plinth, Wall beam &amp; Room Beam</b>					
	Addl Class Room With Hall At Govt Upper Primary schhol, Singhaipali	9.21	Cum	15743.70	144999.00	
<b>E</b>	<b>Roof Slab &amp; Chajja</b>					
	Addl Class Room With Hall At Govt Upper Primary schhol, Singhaipali	10.93	Cum	15009.94	134761.00	
<b>5</b>	<b>Providing MS Reinforcement for RCC work including cutting, bending, binding &amp; tying the grills &amp; placing in position with cost of MS Rod and binding wire of 18 to 20 gauge including cost of all materials, labour, T &amp; P etc. Complete as per direction of the Engineer-in-Charge ( G. Floor)</b>					
	Addl Class Room With Hall At Govt Upper Primary schhol, Singhaipali	32.27	Qnt.	9099.60	293680.00	
<b>6</b>	<b>Brick work with Fly Ash bricks of size 23cmX11cmX8cm and crushing strength not less than 75kg/cm2 in C.M.(1:6) in foundation and plinth including all charges</b>					
	Addl Class Room With Hall At Govt Upper Primary schhol, Singhaipali	24.78	Cum	5364.40	132930.00	
<b>7</b>	<b>Brick work with Fly Ash bricks of size 23cmX11cmX8cm and crushing strength not less than 75kg/cm2 in C.M.(1:4) in super structure including all charges (G. Floor)</b>					
	Addl Class Room With Hall At Govt Upper Primary schhol, Singhaipali	26.00	Cum	5397.80	140343.00	
<b>8</b>	<b>12mm (1/2") thick cement plaster (1:6) over brick work (G.Floor)</b>					
	Addl Class Room With Hall At Govt Upper Primary schhol, Singhaipali	91.88	Sqm	187.10	17191.00	
<b>9</b>	<b>Providing 16 mm thick cement plaster in CM (1:6) finished smooth to inside surface including cost conveyance, royalty, taxes of all materials, labour, T &amp; P etc. complete as per direction of Engineer-in-Charge (G.Floor)</b>					
	Addl Class Room With Hall At Govt Upper Primary schhol, Singhaipali	121.90	Sqm	269.70	32876.00	
<b>10</b>	<b>6mm thick cement plaster (1:4) to RCC surfaces finished smooth including closed deep chipping and slurry treatment (G.Floor)</b>					
	Addl Class Room With Hall At Govt Upper Primary schhol, Singhaipali	60.20	Sqm	208.70	12564.00	

11	Supplying fitting and fixing vetrified tile in floors of size 600mmX 600mm of approved make confirming to IS 13755 laid on 20mm thick cement mortar (1:4) (1cement:4course sand) and filling joints with white cement of approved quality including cost of all materials, labour T & P etc required for the work all complete as per direction of the Engineer-in-Charge (For new work only)					
	Addl Class Room With Hall At Govt Upper Primary schhol, Singhaipali	56.74	Sqm	1141.10	64746.00	
12	Finishing Surface Of Walls With Cement Based Wall Putty & Making Smooth To Recive Painting Including Cost Of Scaffolding Etc. With Cost Of All Material & Labour					
	Addl Class Room With Hall At Govt Upper Primary schhol, Singhaipali	146.52	Sqm	89.60	13128.00	
13	Supplying fitting fixing MS Door and Windows including transport taxes of all materials in G. Floor					
	Addl Class Room With Hall At Govt Upper Primary schhol, Singhaipali	676.20	KG	105.00	71001.00	
14	Priming one coat of wall primer including cost of paint (G.Floor)					
	Addl Class Room With Hall At Govt Upper Primary schhol, Singhaipali	238.4	Sqm	67.20	16020.00	
15	Fixing tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles					
	Addl Class Room With Hall At Govt Upper Primary schhol, Singhaipali	35.58	Sqm	1714.31	60995.00	
16	Painting two coats with water proofing Weather coats of approved shade including cost of paint (G.Floor)					
	Addl Class Room With Hall At Govt Upper Primary schhol, Singhaipali	91.88	Sqm	45.90	4217.00	
17	20 mm thick grading plaster in cm(1:2:2) including all labours T & P and Cost Conveyance of Materials etc. complete					
	Addl Class Room With Hall At Govt Upper Primary schhol, Singhaipali	75.54	Sqm	292.90	22126.00	
18	Painting two coat with SE paint over a coat of primer with approved shade of approved quality including cost of all materials & labour with T & P etc. complete (G Floor)					
	Addl Class Room With Hall At Govt Upper Primary schhol, Singhaipali	45.89	Sqm	160.00	7342.00	

19	Add towards cost of electrification and sanitary fitting with all material			L/S	92000.00	
20	Provision For Black Board and const of Display Board			L/S	13000.00	
				<b>Total</b>	<b>1527772.00</b>	

(Rupees Fifteen Lkhs twenty Seven thousand seven hundred seventy two) Only

Total 20 Items Only

My/our quoted rate is \_\_\_\_\_ % (both figure & words) excess over/less than/equal to above estimated cost.

Notes: (1) The contractor should not write any thing except quoting of percentage and in case of (2) Srtike out which are not applicable

Contractor

Total 20 items only.

No. Of Correction

No. Of Overwriti

No.of interpolation

Approved for 20 items only.

  
Assistant Executive Engineer  
Lakhanpur Block

  
MJE/GRTA  
Lakhanpur Block

  
Block Development Officer  
Lakhanpur

  
Block Development Officer  
Lakhanpur

Signaturte of Contractor