

Construction of GPLF Building with Market Complex, GP-.....*Dilla*.....

BILL OF QUANTITY

Sl. No.	Item of Work	Quantity to be executed	Unit	Rate	Amount
1	2	3	4	5	6
1	Earth work in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing & leveling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering, if necessary from foundation complete as directed by Engineer-in-charge	68.67	Cu.m	269.70	18519.00
2	Filling foundation and plinth with sand including cost conveyance taxes of all material and labour T&P etc. complete in all respect.	74.27	Cu.m	988.34	73406.00
3	Cement concreat (1:3:6) using 4cm size hg metals of approved quality including cost, conveyance, taxes, royalties of all materials, watering & curing for 28 days & cost of all labour with T&P etc. complete.	21.27	Cu.m	6145.34	130684.00
4	Flyash Brick masonry in cement mortar (1:6) in foundation and plinth.	13.73	Cu.m	5772.72	79238.00
5	Flyash Brick masonry in cement mortar (1:6) in Superstructure,etc.	43.59	Cu.m	5863.77	255611.00
6	Flyash Brick masonry in cement mortar (1:6) in Superstructure,etc.	0.39	Cu.m	5863.77	2265.00
7	R.C.C.M-200 using 20 mm and down graded hard granite crusher broken chips,etc.				
a)	Pile Cap	13.78	Cu.m	6278.46	86508.00
b)	Plinth band	7.61	Cu.m	7256.88	55256.00
c)	Column & Beam	12.5	Cu.m	17791.01	222458.00

d)	Lintel	4.14	Cu.m	13107.98	54311.00
e)	Chajja / Roof slab	16.39	Cu.m	13650.97	223795.00
8	Straightening, cutting, bending, binding for steel rods, cranking, hooking, tying the grills & placing in proper position for R.C.C work, including cost of binding wires of 18 to 20 gauge, cost, conveyance, taxes of steel and all other materials, etc., complete.	61.95	One Quintal	9092.89	563281.00
9	2.5cm thick grading concrete of proportion (1:2:2) over roof slab using 12mm to 6mm size cb chips of approved quality including cost, conveyance, taxes & royalty of all materials and labour with T&P etc. complete in all respect.	124.64	1 Sq.m	363.12	45259.00
10	6 mm.thick cement plaster in C.M.(1:4) for ceiling plaster including deep chiping, etc.	77.62	1 Sq.m	212.61	16503.00
11	16 mm thick cement plaster in C.M.(1:6) in internal surface of wall, etc.	324.55	1 Sq.m	277.96	90213.00
12	12 MM (1/2") thick cement plaster in C.M.(1:6) finishing smooth to outside smooth surface of brick walls after racking out the joints including watering and curing with cost, conveyance, royalty and taxes of all materials and cost of all labour charges, cess required for the work etc. complete.	170.52	1 Sq.m	193.89	33061.00
13	Supplying fitting & fixing of MS Door & Window including all cost of material & Laour charges, etc.	1255.75	1Kg	105.00	131854.00
14	Supplying fitting & fixing of PVC Door including all Cost & labour as per direction of E.I.C. (L.S.)	2.00	Each	5500.00	11000.00
15	Fixing tiles in dados skirting & riser of steps on 12mm thick cement plaster 1:3 joined with neat cement slurry mixed with pigments to match the shades of tiles, including rubbing & polishing etc. complete including cost, conveyance, taxes & royalties of all material, labour with T & P complete in all respect.	53.31	1Sq.m	1682.74	89705.00

16	Supplying, fitting and fixing vitrified tile in floors of size 600mm x 600mm of approved make confirming to IS:13756 laid on 20mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all materials, labour with T&P etc required for the work all complete in all respect.	94.42	1Sq.m	1036.36	97853.00
17	Fixing tiles in floors treads or steps and landing on 25mm bed of cement mortar 1:1 (1 cement: 1 sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including rubbing and polishing complete excluding cost of precast tiles per 1 sqm.	9.29	1 Sq.m	1516.57	14089.00
18	Two coats of enamel painting over one coat of primer to doors and windows,etc.	88.53	1Sq.m	182.00	16113.00
19	Finishing walls with water proofing Cement paints of approved shade in new work 2 coats to give an shade including cost of paints.	524.37	1Sq.m	46.07	24159.00
20	Two coats of weather coat of approved quality to out side finishing area,etc.	170.52	1Sq.m	99.64	16990.00
21	Distempering two coats to wall surface with Distemper of app. Shade including cost of all materials and labour with T&P etc complete in all respect.	353.85	1Sq.m	86.61	30647.00
22	Cost of Transperancy board	1.00	Each	8000.00	8000.00
23	Provision for Electrical installation work,etc.	1.00	Each	55000.00	55000.00
24	Provision for Watersupply & Sanitation (Internal) work,etc.	1	Each	76000	76000.00
				GRAND TOTAL	2521778.0

(RUPEES TWENTY FIVE LAKHS TWENTY ONE THOUSAND SEVEN HUNDRED SEVENTY EIGHT) ONLY


Assistant Executive Engineer
Lakhanpur Block


AE/JE/GPTA
Lakhanpur Block

APPROVED FOR 24 (Twenty four) ITEMS ONLY


Block Development Officer
Lakhanpur

My/our quoted rate is % (both in figures and words) excess over / less than / equal to the above estimated cost.

Signature of Tenderer |

NOTES :-

1. The contractor should not write anything excepting quoting of percentage and in any case
2. Percentage quoted by the tenderer shall be accurately filled in words and in figures..
3. Strike out which is not applicable. If the tenderer quotes the percentage without mentioning
4. Percentage should be quoted up to (one) digit after the decimal point. If the tenderer writes
5. Rate of all items are inclusive of cost, carriage, royalty, cess and other taxes of materials.

Tenderer

No. of corrections.....

No. of Over writings.....

No. of Interpolations.....

Signature of Tenderer |