

**Construction of Girls Common Room for Mahima Degree College, Bijapali  
Panchgaon**

**BILL OF QUANTITY**

Sl. No.	Item of Work	Quantity to be executed	Unit	Rate	Amount
1	2	3	4	5	6
1	Bricks work with fly ash bricks ( 23cm x 11 CM x 8 CM) size having crushing strength not less than 75 kg/cm with dimensional tolerance 2% in cement mortar (1:6) in superstructure including splays, cutting, circular molding, watering & curring for 7 days	3.64	Cu.m	5336.25	19423.95
2	Reinforced cement concrete work of M-20 grade with 20 mm & down grade black hard granite (crusher broken) stone chips including hoisting & laying including cost, conveyance, taxes & royalty of all materials and labour	6.04	Cu.m	6180.74	37331.67
3	Reinforced cement concrete work of M-25 grade with 20 mm & down grade black hard granite (crusher broken) stone chips including hoisting & laying including cost, conveyance, taxes & royalty of all materials and labour	20.37	Cu.m	6565.24	133733.94
4	Providing MS reinforcement for RSS work including Straightening, cutting, bending, binding tor steel rods, cranking, hooking, tying the grills & placing in proper position for R.C.C work, including cost of binding wires of 18 to 20 gauge, cost, conveyance, taxes of steel and all other materials,etc., complete.	23.55	Qntl	8442.29	198815.93
5	Rigid and smooth centering and shuttering for RCC work including false work and dismantalling them after casting including cost of materials etc complete (1st floor)				
a)	Lintel	14.74	Sqm	703.94	10376.08
B	Roof slab & Chajja	144.75	Sqm	1065.84	154280.34
C	Beam & Coloum	47.89	Sqm	1402.86	67182.97
6	2.5cm thick grading concrete of proportion (1:2:2) over roof slab using 12mm to 6mm size cb chips of approved quality including cost, conveyance, taxes & royalty of all materials and labour with T&P etc. complete in all respect.	123.23	Sqm	343.96	42386.19

7	12 MM (1/2") thick cement plaster in C.M.(1:6) finishing smooth to outside smooth surface of brick walls after racking out the joints including watering and curing with cost, conveyance, royalty and taxes of all materials and cost of all labour charges, cess required for the work etc. complete.	85.61	Sqm	166.11	14220.68
8	16 MM (5/8") thick cement plaster in C.M.(1:6) finishing smooth to inside rough surface of 9" x 10" brick walls after racking out the joints including watering and curing with cost, conveyance, royalty and taxes of all materials and cost of all labour charges, cess required for the work etc. complete.	149.07	Sqm	232.32	34631.94
9	6 mm.thick cement plaster in C.M.(1:4) over RCC surface with slury treatment for finishing	106.90	sqm	177.60	18985.44
10	Finishing wall surface with Arcrylic wall putty of approved make and finished smooth to receive painting including cost of all material labour etc complete	106.85	sqm	79.85	8531.97
11	Supplying fitting & fixing of MS Door & Window including all cost of material & Laour charges, etc.	844.93	Kgs	95.00	80268.35
12	Supplying, fitting and fixing vitrified tile in floors of size 600mm x 600mm of approved make confirming to IS:13756 laid on 20mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all materials, labour with T&P etc required for the work all complete in all respect.	106.90	sqm	1087.64	116268.72
13	Supplying, laying and fixing vertified tiles in dados, skirting and risers of steps on 12 MM thick Plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including ribbing and	6.24	sqm	1760.44	10985.15
14	White washing two coats to wall surface including cost of all materials complete	186.22	sqm	12.88	2398.51
15	Finishing walls with water proofing weather coat painting two coats with any approved shade including cost of paint	85.59	sqm	79.30	6787.29
16	Distempering two coats to wall surface with distemper od app shade including cost of all materials and labour with T & P etc complete in all respect	255.97	sqm	122.24	31289.77

17	Painting two coats to D & W over a coat of priming with any approved paint including cost of paint	37.10	sqm	231.31	8581.60
				<b>TOTAL</b>	<b>996480.5</b>
18	Electrification				<b>10000.0</b>
19	Display Board				<b>10000.0</b>
				<b>Grand Total</b>	<b>1016480.5</b>
				<b>Or say</b>	<b>1016480.0</b>

(Rupees Ten lakhs sixteen thousand four hundred eighty) ONLY

  
Assistant Executive Engineer  
Lakhanpur Block

  
AE/JE/GPTA  
Lakhanpur Block

APPROVED FOR 19 (Nineteen) ITEMS ONLY

  
Block Development Officer  
Lakhanpur

My/our quoted rate is ..... % (both in figures and words) excess over / less than / equal to the above estimated cost.

Signature of Tenderer |

**NOTES :-**

1. The contractor should not write anything excepting quoting of percentage and in any case
2. Percentage quoted by the tenderer shall be accurately filled in words and in figures..
3. Strike out which is not applicable. If the tenderer quotes the percentage without
4. Percentage should be quoted up to (one) digit after the decimal point. If the tenderer
5. Rate of all items are inclusive of cost, carriage, royalty, cess and other taxes of materials.

**Tenderer**

No. of corrections.....  
No. of Over writings.....  
No. of Interpolations.....

Signature of Tenderer |