

## BOQ

**Tender Inviting Authority: BDO, Lakhanpur**

**Name of Work: Extension of Panchayat Samiti Office Building, Lakhanpur**

### PRICE SCHEDULE

(this BOQ templete must be modified/ replaced by the bidder and the same should be uploaded after filling the relevant coulumn, else the bidder is liable to be rejected for this tender . Bidders are allowed to enter the Bldder Name and Values only)

Sl. No.	Item Description	Quantity	Units	Estimated Rate	Total Amount Without Taxes	Total Amount in Words
1	Earth work in excavation in foundation in all kinds of soil with all leads and lifts including dressing and levelling the bed in layers not exceeding 0.3 m in depth including dewatering if necessary with cost of all labour and T & P work etc. Complete as per direction of Engineer-in-charge					
		84.46	cum	270.90	22880.00	
2	Supplying filling in F & P with clean course good river sand including watering, ramming, poking & compacting & cost, conveyance royalties, taxes of all materials, labour, T & P etc. Complete as per direction of Engineer-in-Charge					
		57.77	cum	988.34	57096.00	
3	Providing and laying PCC of (1:3:6) with 2.5cm to 4cm size crusher broken hard black granite metal with cost, conveyance, royalties, taxes of all materials, all labour, T & P etc. Complete as per direction of Engineer-in-charge					
		28.58	cum	5903.08	168710.00	
4	Providing and laying RCC work in M-20 grade with 20mm and down grade black hard granite crusher broken stone chips of approved quality from quarry with smooth centering and shuttering hoisting and laying in layers including cost. Conveyance, royalty and taxes of aal materials, labour, T & P etc. complete as per direction of the Engineer-in-charge					
A	Column Base footing					
		22.72	Cum	7256.88	164876.00	
B	Plinth Bend					
		8.06	Cum	7256.88	58490.00	
C	Lintel Beam Column Above Plinth, Wall beam & Room Beam					

		10.60	Cum	13107.98	138945.00	
<b>RCC M 25</b>						
<b>E</b>	<b>Roof Slab &amp; Chajja</b>					
		28.14	Cum	14311.92	402737.00	
	<b>Column and roof beam</b>					
		8.25	Cum	18451.96	152229.00	
<b>5</b>	<b>Providing MS Reinforcement for RCC work including cutting, bending, binding &amp; tying the grills &amp; placing in position with cost of MS Rod and binding wire of 18 to 20 gauge including cost of all materials, labour, T &amp; P etc. Complete as per direction of the Engineer-in-Charge ( G. Floor)</b>					
		66.11	Qnt.	9092.89	601131.00	
<b>6</b>	<b>Brick work with Fly Ash bricks of size 23cmX11cmX8cm and crushing strength not less than 75kg/cm<sup>2</sup> in C.M.(1:6) in foundation and plinth including all charges</b>					
		36.98	Cum	5772.72	213475.00	
<b>7</b>	<b>Brick work with Fly Ash bricks of size 23cmX11cmX8cm and crushing strength not less than 75kg/cm<sup>2</sup> in C.M.(1:4) in super structure including all charges (G. Floor)</b>					
		67.52	Cum	5863.77	395922.00	
<b>8</b>	<b>12mm (1/2") thick cement plaster (1:6) over brick work (G.Floor)</b>					
		303.69	Sqm	193.89	58882.00	
<b>9</b>	<b>Providing 16 mm thick cement plaster in CM (1:6) finished smooth to inside surface including cost conveyance, royalty, taxes of all materials, labour, T &amp; P etc. complete as per direction of Engineer-in-Charge (G.Floor)</b>					
		323.15	Sqm	277.96	89823.00	
<b>10</b>	<b>6mm thick cement plaster (1:4) to RCC surfaces finished smooth including closed deep chipping and slurry treatment (G.Floor)</b>					
		135.03	Sqm	212.61	28709.00	

11	Supplying fitting and fixing vetrified tile in floors of size 600mmX 600mm of approved make confirming to IS 13755 laid on 20mm thick cement mortar (1:4) (1cement:4course sand) and filling joints with white cement of approved quality including cost of all materials, labour T & P etc required for the work all complete as per direction of the Engineer-In-Charge (For new work only)	192.92	Sqm	1516.57	292577.00
12	Finishing Surface Of Walls With Cement Based Wall Putty & Making Smooth To Recive Painting Including Cost Of Scaffolding Etc. With Cost Of All Material & Labour	778.18	Sqm	133.18	103638.00
13	Supplying fitting fixing MS Door and Windows Including transport taxes of all materials In G. Floor	816.00	KG	90.00	73440.00
14	Finishing walls with water proofing weather coat paint	338.69	Sqm	99.64	33747.00
15	Cement washing one coat with white cement	702.23	Sqm	31.42	22064.00
16	Distempering two coats to walls with distemper of any approved	458.18	Sqm	86.61	39683.00
17	25 mm thick grading plaster In cm(1:2:2) Including all labours T & P and Cost Conveyance of Materials etc. complete	204.96	Sqm	363.12	74425.00
18	Painting two coat with SE paint over a coat of primer with approved shade of approved quality including cost of all materials & labour with T & P etc. complete (G Floor)	65.23	Sqm	182.00	11872.00
19	Add towards cost of electrification and sanitary fitting with all material			L/S	140000.00

20				L/S	7300.00	
	Provision For const of Display Board					
				Total	3352651.00	

(Rupees Thirty Three Lakh Fifty Two Thousand Six Hundred Fifty One) Only

  
Assistant Executive Engineer  
Lakhanpur Block

  
AE/LE/SP/A  
Lakhanpur Block  
APPROVED FOR 20 (Twenty) ITEMS ONLY

  
Block Development Officer  
Lakhanpur

My/our quoted rate is ..... % (both in figures and words) excess over / less than / equal to the above estimated cost.

Signature of Tenderer

**NOTES :-**

1. The contractor should not write anything excepting quoting of percentage and in any case
2. Percentage quoted by the tenderer shall be accurately filled in words and in figures..
3. Strike out which is not applicable. If the tenderer quotes the percentage without mentioning
4. Percentage should be quoted up to (one) digit after the decimal point. If the tenderer writes more
5. Rate of all items are inclusive of cost, carriage, royalty, cess and other taxes of materials.

**Tenderer**

No. of corrections.....  
No. of Over writings.....  
No. of Interpolations.....