

BOQ

Tender Inviting Authority: BDO, Lakhanpur

Name of Work: construction of kalyan mandap at Lakhyaghar Ganda Samaj

PRICE SCHEDULE

(this BOQ templete must be modified/ replaced by the bidder and the same should be uploaded after filling the relevant coulumns, else the bidder is liable to be rejected for this tender . Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	Quantity	Units	Estimated Rate	Total Amount Without Taxes	Total Amount in Words
1	Earth work in excavation in foundation in all kinds of soil with all leads and lifts including dressing and levelling the bed in layers not exceeding 0.3 m in depth including dewatering if necessary with cost of all labour and T & P work etc. Complete as per direction of Engineer-in-charge					
	construction of kalyan mandap at Lakhyaghar Ganda Samaj	65.8	cum	276.89	18219.36	
2	Supplying filling in F & P with clean course good river sand including watering, ramming, poking & compacting & cost, conveyance royalties, taxes of all materials, labour, T & P etc. Complete as per direction of Engineer-in-Charge					
	construction of kalyan mandap at Lakhyaghar Ganda Samaj	22.64	cum	989.78	22408.62	
3	Providing and laying PCC of (1:3:6) with 2.5cm to 4cm size crusher broken hard black granite metal with cost, conveyance, royalties, taxes of all materials, all labour, T & P etc. Complete as per direction of Engineer-in-charge					
	construction of kalyan mandap at Lakhyaghar Ganda Samaj	15.27	cum	6594.05	100691.14	
4	Providing and laying RCC work in M-20 grade with 20mm and down grade black hard granite crusher broken stone chips of approved quality from quarry with smooth centering and shuttering hoisting and laying in layers including cost. Conveyance, royalty and taxes of aal materials, labour, T & P etc. complete as per direction of the Engineer-in-charge					
A	Column Base footing					
	construction of kalyan mandap at Lakhyaghar Ganda Samaj	12.69	Cum	8191.07	103944.68	
B	Plinth Bend					
	construction of kalyan mandap at Lakhyaghar Ganda Samaj	6.02	Cum	8191.07	49310.24	
C	Lintel Beam					

	construction of kalyan mandap at Lakhyaghar Ganda Samaj	2.41	Cum	15230.82	36706.28	
D	Column Above Plinth, Wall beam & Room Beam					
	construction of kalyan mandap at Lakhyaghar Ganda Samaj	4.60	Cum	19150.74	88093.40	
E	Roof Slab stair, & wall beam					
F	construction of kalyan mandap at Lakhyaghar Ganda Samaj	18.93	Cum	14815.34	280454.39	
G	chajja	0.59	Cum	15230.82	8986.18	
H	room beam	2.40	Cum	19150.74	45961.78	
5	Providing MS Reinforcement for RCC work including cutting, bending, binding & tying the grills & placing in position with cost of MS Rod and binding wire of 18 to 20 gauge including cost of all materials, labour, T & P etc. Complete as per direction of the Engineer-in-Charge (G. Floor)					
	construction of kalyan mandap at Lakhyaghar Ganda Samaj	45.32	Qnt.	9063.46	410756.01	
6	Brick work with Fly Ash bricks of size 23cmX11cmX8cm and crushing strength not less than 75kg/cm2 in C.M.(1:6) in foundation and plinth including all charges					
	construction of kalyan mandap at Lakhyaghar Ganda Samaj	24.42	Cum	6005.51	146654.55	
7	Brick work with Fly Ash bricks of size 23cmX11cmX8cm and crushing strength not less than 75kg/cm2 in C.M.(1:4) in super structure including all charges (G. Floor)					
	construction of kalyan mandap at Lakhyaghar Ganda Samaj	20.58	Cum	6038.51	124272.54	
8	12mm (1/2") thick cement plaster (1:6) over brick work (G.Floor)					
	construction of kalyan mandap at Lakhyaghar Ganda Samaj	178.34	Sqm	203.67	36322.51	
9	Providing 16 mm thick cement plaster in CM (1:6) finished smooth to inside surface including cost conveyance, royalty, taxes of all materials, labour, T & P etc. complete as per direction of Engineer-in-Charge (G.Floor)					
	construction of kalyan mandap at Lakhyaghar Ganda Samaj	121.90	Sqm	269.70	32876.00	

10	wall painting one coat with any approved primer on new plaster					
	construction of kalyan mandap at Lakhyaghar Ganda Samaj	298.47	Sqm	68.39	20412.36	
11	Supplying fitting and fixing vetrified tile in floors of size 600mmX 600mm of approved make confirming to IS 13755 laid on 20mm thick cement mortar (1:4) (1cement:4course sand) and filling joints with white cement of approved quality including cost of all materials, labour T & P etc required for the work all complete as per direction of the Engineer-in-Charge (For new work only)					
	construction of kalyan mandap at Lakhyaghar Ganda Samaj	103.45	Sqm	1316.64	136206.41	
12	Finishing Surface Of Walls With Cement Based Wall Putty & Making Smooth To Recive Painting Including Cost Of Scaffolding Etc. With Cost Of All Material & Labour					
	construction of kalyan mandap at Lakhyaghar Ganda Samaj	172.58	Sqm	157.85	27241.75	
13	Supplying fitting fixing MS Door and Windows including transport taxes of all materials in G. Floor					
	construction of kalyan mandap at Lakhyaghar Ganda Samaj	1207.50	KG	105.00	126787.50	
14	Priming one coat of wall primer including cost of paint (G.Floor)					
	construction of kalyan mandap at Lakhyaghar Ganda Samaj	120.12	Sqm	87.68	10532.12	
15	Fixing tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles					
	construction of kalyan mandap at Lakhyaghar Ganda Samaj	10.76	Sqm	1316.13	14161.56	
16	Painting two coats with water proofing Weather coats of approved shade including cost of paint (G.Floor)					
	construction of kalyan mandap at Lakhyaghar Ganda Samaj	178.34	Sqm	91.52	16321.68	
17	20 mm thick grading plaster in cm(1:2:2) Including all labours T & P and Cost Conveyance of Materials etc. complete					
	construction of kalyan mandap at Lakhyaghar Ganda Samaj	112.87	Sqm	418.15	47196.59	

18	Painting two coat with SE paint over a coat of primer with approved shade of approved quality including cost of all materials & labour with T & P etc. complete (G Floor)					
	construction of kalyan mandap at Lakhyaghar Ganda Samaj	45.89	Sqm	160.00	7342.00	
19	Add towards cost of electrification and sanitary fitting with all material			L/S	200000.00	
20	Provision For Aluminium sliding window and Display Board			L/S	50200.00	
				Total	2162060.00	

(Rupees Tweny one Lakh Sixty Two Thousand Sixty) Only

Total 20 Items Only

My/our quoted rate is _____ % (both figure & words) excess over/less than/equal to above estimated cost.

Notes: (1) The contractor should not write any thing except quoting of percentage and in case of (2) Srtike out which are not applicable

Contractor

Total _____ items only.

No. Of Correction

No. Of Overwriti

No.of interpolation

Approved for _____ items only.


Assistant Executive Engineer
Lakhanpur Block


Lakhanpur Block


Block Development Officer
Lakhanpur


Block Development Officer
Lakhanpur

Signaturte of Contractor