


AUTHORITY INVITING TENDER:- PROJECT ADMINISTRATOR,ITDA, JHARSUGUDA

BOQ FOR THE WORK :- CONSTRUCTION OF APPROCH ROAD IN BLOCK LAIKERA FOR THE YEAR 2025-26						
item no	Item of Work	Qty	Unit	Rate in Figure	Rate in words	Amount
1	Excavation for road work in soil with hydraulic excavator of 0.9cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes in accordance with requirements of lines, grades and cross sections and transporting to the embankment locations with all lifts & leads up to 1000m.as per approved Drawing & Technical Specifications and as per Clause - 301 of MoRT&H Specifications for Road & Bridge works (5th Revision).	1267.880	Cum	Rs. 74.79	Rupees Seventy Four And Paise Seventy Nine Only.	Rs. 94,825.00
2	Loosening, leveling and Compacting original ground supporting embankment to facilitate placement of first layer of embankment, scarified to a depth of 150mm, mixed with water at OMC and then compacted by rolling so as to achieve minimum dry density as given in Table 300-2 for embankment construction as per Technical Specifications and as per Clause - 305.3.4 of MoRT&H Specifications for Road & Bridge works (5th Revision).	253.580	Cum	Rs. 36.05	Rupees Thirty Six And Paise Five Only.	Rs. 9,142.00
3	Providing G.S.B. Gr-VI stone screening materials, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC and compacting with vibratory roller to achieve the desired density, as per approved Drawing & Technical Specifications and as per Clause - 401 of MoRT&H Specifications for Road & Bridge works (5th Revision) including cost, conveyance, royalty & other taxes of materials, cost of labour, machinery, T&P etc complete.	1037.590	Cum	Rs. 2,353.56	Rupees Two Thousand Three Hundred Fifty Three And Paise Fifty Six Only.	Rs. 24,42,030.00
4	Providing, Laying, spreading and compacting graded stone aggregate to Wet Mix Macadam specification including premixing the material with water at OMC in mechanical mix plant carriage of mixed materia by tripper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibrator roller to acchive the desired density as per approved drawing & technical specification and as per cluse -406 of MoRT & H specifications for road and Bridge works (5th Revision) including cost conveyance, royalty & other taxes of materials, cost of labour, machinery, T & P etc. complete	344.140	Cum	Rs. 2,505.59	Rupees Two Thousand Five Hundred Five And Paise Fifty Nine Only.	Rs. 8,62,274.00
5	Providing dry lean cement concrete sub-base with mechanised method and finished including cost, conveyance, royalty of all materials, cost of labour & hire charges of machineries, as per approved Drawing, Design & Technical Specifications complete as per clause - 601 of MoRT&H Specifications for Road & Bridge works (5th Revision) including cost, conveyance, royalty & other taxes of materials, cost of labour, machinery, T&P etc complete.	219.938	Cum	Rs. 3,974.68	Rupees Three Thousand Nine Hundred Seventy Four And Paise Sixty Eight Only.	Rs. 8,74,181.00


04/10/25

Technical Consultant
ITDA, Jharsuguda


Asst. Executive Engineer,
ITDA, Jharsuguda


Project Administrator,
ITDA, Jharsuguda

Item no	Item of Work	Qty	Unit	Rate in Figure	Rate in words	Amount
6	Providing cement concrete pavement of M-30, adopting mechanised method and finished including cost, conveyance, royalty of all materials, cost of labour & hire charges of machineries, as per approved Drawing, Design & Technical Specifications complete as per clause - 602 of MoRT&H Specifications for Road & Bridge works (5th Revision) including cost, conveyance, royalty & other taxes of materials, cost of labour, machinery, T&P etc complete.	408.830	Cum	Rs. 6,806.65	Rupees Six Thousand Eight Hundred Six And Paise Sixty Five Only.	Rs. 27,82,763.00
7	Rigid and smooth Centering and shuttering for R.C.C.Works and dismantling then after casting including cost of all materials complete.	1138.500	Sqm	Rs. 246.21	Rupees Two Hundred Forty Six And Paise Twenty One Only.	Rs. 2,80,310.00
8	Add Cost For Transparency Board & Photography	1.000	Unit	Rs. 10,000.00	Rupees Ten Thousand Only.	Rs. 10,000.00
G. TOTAL						Rs. 73,55,525.00
(Rupees Seventy Three Lakh Fifty Five Thousand Five Hundred Twenty Five) Only.						


 04/10/23
 Technical Consultant
 ITDA, Jharsuguda
Technical Consultant
ITDA, Jharsuguda


 Asst Executive Engineer
 ITDA, Jharsuguda
Asst. Executive Engineer,
ITDA, Jharsuguda


 Project Administrator
 ITDA, Jharsuguda
Project Administrator,
ITDA, Jharsuguda

My/ our quoted rate is _____ % (both figure & words) excess over/ less than /equal to above estimated cost.

Signature of the tenderer

Notes:- (1) The contractor should not write any thing except quoting of percentage and in case of any
 (2) Strike out which are not applicable.

Signature of the tenderer


 Project Administrator
 ITDA, Jharsuguda
Project Administrator,
ITDA, Jharsuguda

Total-08 (Eight) items only.

No. of Correction

No. of Overwriting

No of interpolation

Approved for 08 (Eight) Items only.

Signature of Contractor


 Project Administrator
 ITDA, Jharsuguda
Project Administrator,
ITDA, Jharsuguda