

**DISTRICT RURAL DEVELOPMENT AGENCY  
JHARSUGUDA**



**PR & DW DEPARTMENT, ODISHA  
BID DOCUMENT**

Name of the Work : Extension and Repair of DDL  
Building

Name of the Block : Jharsuguda

Name of the District : Jharsuguda

Estimated Cost : Rs 2,750,000.00

Tender Value : Rs 

1,816,534.00
--------------



4	Fly Ash Brick masonry in cement mortar (1:6) in F&P with best quality bricks having crushing strength no less than 75 kg/sq.cm with dimensional tolerance # 2% immersing the bricks in water for not less than 6 hours before use( the bricks shall be well burnt, free from cracks, well shaped,uniform in size and shall produce a clear ringing sound when struck) includes moulding, chamfering, corbelling etc. complete as per drawing, design and specification, watering and curing for seven days incl. cost , conveyance, and taxes of all materials, labour T&P etc.	30.276	Cum	5788.2	Rupees five thousand seven hundred eightyeight and twenty paise only	175243.54
5	Fly Ash Brick masonry in cement mortar (1:6) in Super-structure with best quality bricks having crushing strength no less than 75 kg/sq.cm with dimensional tolerance # 2% immersing the bricks in water for not less than 6 hours before use( the bricks shall be well burnt, free from cracks, well shaped,uniform in size and shall produce a clear ringing sound when struck) includes moulding, chamfering, corbelling etc. complete as per drawing, design and specification, watering and curing for seven days incl. cost , conveyance, royalty and taxes of all	54.06	Cum	5821.5	Rupees five thousand Eight hundred twenty oneand fifty paise only	314710.29
6	R.C.C work M-20 grade concrete having minium compressive strength 200Kg/cm <sup>2</sup> in 15cm cubes at 28days after mixing and test conducted in accordance with IS 456 and IS 516 using 20mm &10mm size black hard crusher broken granite chips incl. hoisting lowering laying and compacting concrete by using vibrator with watering and curing for 28days centring shuttering and finishing the exposed surface smooth providing groves or beds wherever necessary including cost , conveyance royalties and all taxes and cost of all materials and labour with T&P					
a	column base and plinth beam	11.687	cum	7549.00	Rupees Seven thousand five hundred fourty nine only	88227.05
b	column and beam	6.9668	cum	18347.70	Rupees eighteen thousand three hundredfourty seven and seventy paise only	127825.31

c	lintel	2.5979	cum	14340.40	Rupees fourteen thousand three hundred fourty and fourty paise only	37254.21
d	slab	16.122	cum	13924.90	Rupees thirteen thosand nine hundred twenty four and ninety only	224495.85
5	Straightening, cutting, bending and binding, welding and jointing (if necessary) coiled/bentup MS Rod/HYSD rods etc. including hoisting, placing in position, tying the grills binding with 18 to 20 gauge binding wires required for R.C.C works, cost of all labours T&P etc. as required for the work complete as directed by E.I.C	29	Qtl	8879.75	Rupes eight thousand eight hundred and seventy nine and seventy five paise only	257512.75
6	12 mm (½") thick cement plaster (1:6) with neat cement punning in finished smooth brick walls and skirting after racking out the joints including watering and curing complete with cost conveyance royalties and all taxes of all materials and cost of all labour with T & P required for the work	162.76	Sqm.	192.10	Rupees one hundred ninety two and ten paise only	31265.43
7	Providing 16 mm thick cement plaster to the inside surface of brick masonry wall with cement mortar (1:6) including racking out of joints, scraping and cleaning the surface with finishing the plaster surface smooth using wooden floats only to the proper plumbs and materials & all taxes, royalties, watering & curing etc. complete	253.53	Sqm.	276.80	rupes Two hundred seventy six and Eighty paise only	70177.10
8	6mm thick cement plaster (1:4) to Rcc surface Finished smooth including close deep chipping etc complete	82.6	Sqm.	202.55	Rupes Two hundred two and fifty five paise only	16730.63
9	Supplying, fitting and fixing Vetrified tile in floors of size 600 mm x 600 mm of approved make confirming to IS 13755 laid on 20 mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all matrials. Labour T&P etc. required for the work all complete as per direction of the	82.6	Sqm.	1058.65	Rupees one thousand fifty eight and sixty five paise only	87444.49

10	Supplying, fitting and fixing Vetrified tile in dados ,skirting and rise of step of size 600 mm x 600 mm of approved make confirming to IS 13755 laid on 12 mm thick cement mortar (1:3) and filling joints with white cement of approved quality including cost of all matrials. Labour T&P etc. required for the work all complete as per direction of the Engineer- in- Charge	70.02	Sqm.	1198.15	One thousand one hundred Ninety eight and fifteen paise only	83894.46
11	Supplying fitting & fixing MS doors Windows incl all labours T & P etc.	405.00	Kg	100.00	Rupees one hundred only	40500.00
12	Painting two coat with S.E paint over a coat of primer with approved shade of approved quality including cost of all materials & labour with T&P etc. complete.	44.60	Sqm.	187.94	Rupees one hundred eight seven and ninety four paise only	8381.18
13	White washing one coats to wall surface including cost of all materials and labour with T&P etc complete in all respect.	498.89	Sqm.	48.75	Rupees fourty eight and seventy five paise only	24320.69
14	Distemping two coats over a coat primer with any approved shade over the interior surface of walls etc complete in all floors as directed by the Engineer-in-Charge over a coat of chalk washing using distemper including cost conveyance of all materials including cost of distemper with all taxes and cost of all labour with T&P required for the work etc complete in all respect	336.13	Sqm.	87.95	Rupees eightyseven and ninty five paise only	29562.63
15	Finishing walls with water-proofing weather coat over acoat primerof approved shade on new work to give an even shade including cost of cement paint with conveyance,sundries T&P etc	162.76	Sqm.	97.30	Rupees Ninety seven and thirty paise only	15836.16
16	Costruction of Display board	1.00	Nos	6500.00	Six thousand five hundred only	6500.00
						1798548.89
						17985.00
17	Work Contingency 1%					1816533.89
				<b>Total</b>		<b>1816533.89</b>
				<b>Say Rs</b>		<b>1816534.00</b>
	<b>Seventeen (17) nos. only</b>					

**Eighteen lakh Sixteen thousand Five hundred Thirty four only**

*R. Malharani*  
Assistant Engineer  
Jharsuguda Block

*16/09/20*  
Assistant Exe Engineer  
Jharsuguda Block

*[Signature]*  
Block Development Officer  
Jharsuguda Block

My/ our quoted rate is \_\_\_\_\_ % (both figure & words) excess over/ less than /equal to above estimated cost.

**Signature of the tenderer**

- 1 The contractor should not write any thing except quoting of percentage and in case of any thing else regarding tender.
- 2 Strike out which are not applicable.
- 3 Percentage quoted by the contractor shall be accurately filled in figures and words so there is no discrepancy.
- 4 If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
- 5 The percentage quoted in the tender without mentioning excess or less will be treated as excess.
- 6 The contractor will write percentage excess or less upto one decimal point only. If he writes the percentage excess or less upto two or more decimal point shall only be considered.

**Signature of the tenderer**

Total-17 (seventeen) items only.

No. of Correction  
No. of Overwriting  
No. of

Interpolation

Approved for - 17(seventeen)Items only.

**Signature of Contractor**

APPROVED  
For 17( seventeen) item Only

  
Block Development Officer  
Jharsuguda

  
Block Development Officer  
Jharsuguda