

## TENDER SCHEDULE

1	Name of Work	<b>CONSTRUCTION &amp; HEIGHTENING OF BOUNDRYWALL ALONG WITH BARBED WIRE FENCING FOR GIRLS HOSTEL AT TAREIKELA SEVASHRAM SCHOOL</b>
2	Estimated cost	
3	Amount Put to Tender	Rs.3000000/-
4	Earnest Money Deposit E.M.D. (1%)	Rs.25,21,0008/-
5	Class of Contractor	Rs.25210/-
6	Cost of tender paper	" B" & "C" Class
7	Period of completion	Rs. 6000/-
8	Last Date of Sale of tender paper	Three Celender months
9	Last Date and Time of receipt of tender paper	
10	Date and Time of opening of tender paper	

### BOQ

### CONSTRUCTION & HEIGHTENING OF BOUNDRYWALL ALONG WITH BARBED WIRE FENCING FOR GIRLS HOSTEL AT TAREIKELA SEVASHRAM SCHOOL

Sl no	Particulars	Qty	Unit	Rate	Amount
1	Earthwork excavation in hard soil within Initial lead and initial lift including rough dressing and levelling the foudation bed and depositing the excavted earth away from work site etc.compelte	124.69	Per Cum	276.89	34525.00
2	Filling foundation and plinth with well watered and rammed sand including all cost, conveyance and royalty of all materials etc.	16.95	Per Cum	701.80	11896.00
3	Cement concrete (1:3:6)with 4cm size Crusher broken granite metal including all cost, conveyance and royalty of all materials etc.	25.43	Per Cum	5904.50	150151.00
4	Cement concrete in M20 grade using 20 mm down graded size crusher broken granite metal of approved quality quarried and free from weathered skin and foreign materials including mixing the materials by use of concrete mixtures and laying concrete in layers not exceeding 0.15 m in depth to required level curing vibrating with vibrators, finishing etc with all leads lifts and delifts complete in all respect to proper profile and leveling including dewatering if necessary and cost, conveyance and royalty and other taxes etc of materials including hire & running charges of the machineries complete .				
	a) RCC Plinth Beam	9.22	Per Cum	6366.85	58702.00
	b) RCC Column & Beam	44.14	Per Cum	15634.30	690098.00
5	Straightening, cutting, bending, binding and tying the grills as per approved design and placing them in position including cost of binding wire 18 to 20 gauge and including cost and conveyance of HYSD rods etc complete as directed by the Engineer - In - Charge.	53.36	Per Qntl	8901.19	474967.00
6	Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. in cement mortar (1:6) in foundation and plinth including cost conveyance & royalty of the materials etc complete	54.13	Per Cum	5426.70	293747.00
7	Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. in cement mortar (1:6) in superstructure including cost conveyance & royalty of the materials etc complete	76.07	Per Cum	5459.70	415319.00
8	Cement plaster 16 mm thick C.P. in C.M.(1:6) for brick work to 12 mm deep including watering and curing and finishing including cost, conveyance royalty etc.	855.51	Per Sqm	274.00	234409.00
9	Priming with wall cement primer (water bound) of approved shade on new work to give an even shade excluding cost of primer etc complete.	855.51	Per Sqm	80.60	68954.00

10	Weather.Coat two coats to walls with weather coat of approved hade on new work to give an even shade including cost of weather coat.	855.51	Per Sqm	97.30	83240.00
11	Add Cost of Signboard				5000.00
Total 11 ( Eleven) Items			Total	Rs.	2521008.00
			Total	Rs.	2521008.00

( Rupees Twenty Five Lakh Twenty One Thousand Eight ) only  
G.S.T 18% will be paid extra

Rate to be Quoted in terms of % (Percentage) Less than /excess over/Schedule of rate over the amount put to tender amount as given above. (Both in words & Figures)	
Approved for	
Total :11 ( Eleven ) items only	
1	Total No. of Corrections.....
2	Total No. of Overwritings.....
3	Total No. of Interpolations.....
4	E.M.D. Furnished/ EMD Exempted
	a) Demand Draft No .....
	b) Amount Rs.....
5	Copy of Pan Card : furnished/ not furnished
6	Copy of G.S.T Liciance : furnished/ not furnished
7	Copy of Contractor's licence : furnished/not furnished
8	Copy of Experiance Certificate :furnished/ not furnished
9	Total No. of sheets in the Tender Papers : .....

.....Schedule of Rate

.....

.....% excess or

.....% less

Full signature of the Contractor

ASST. ENGINEER  
ITDA, JHARSUGUDA  
Asst. Engineer,  
ITDA, Jharsuguda

ASST. EXECUTIVE ENGINEER  
ITDA, JHARSUGUDA  
Asst. Executive Engineer,  
ITDA, Jharsuguda

PROJECT ADMINISTRATOR  
ITDA, JHARSUGUDA  
Project Administrator,  
ITDA, Jharsuguda