

Name of the Work "Construction of Addl. Class Room and Girls Toilet at Laikera Degree College ,Laikera G.P.

TENDER SCHEDULE

SI NO	Description of Item	Unit	Quantity	Rate	Amount
1	Fly ash Brick Masonry in C.M. (1:6) with all Finishing, Curing in superstructure etc. complete	cum	23.16	6081.90	140857.00
2	R.C.C. M-20 Grade With 20mm and down Grade C.B. Chips of approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator watering, curing and cost of all materials and labour, T & P etc Complete but excluding cost of reinforcement complete.	cum	25.060	6215.50	155776.00
3	Rigid and smooth centering and shuttering for R.C.C. work and dismantling then after casting including cost of all materials complete				
	(A) Lintel	Sqm	8.080	682.00	5511.00
	(B) Column & Beam	Sqm	59.760	1431.06	85520.00
	(C) Roof slab & Chajja	Sqm	140.860	905.44	127540.00
4	Providing M.S. reinforcement for R.C.C. work including cutting, bending, binding and tying the grills and placing in position including cost of binding wire 18 to 20 gauge and cost and carriage of steel. etc. complete.	Qtnl	23.81	8886.30	211577.00
5	12mm thick C.P. in C.M (1:6) Over brick Masonary to the smooth surface including watering, Curing, cost, carriage, royalty and taxes of all materials, cost of all labour T&P etc. complete as per the direction of E.I.C.	Sqm	101.69	202.40	20582.00
6	16mm thick C.P. in C.M. (1:6) over brick masonry to the rough surface including watering, curing cost, Carriage, royalty and taxes of all materials, cost of all labour, T&P	Sqm	217.24	286.90	65384.00
7	6mm thick cement plaster (1:4) to RCC surfaces finisher smooth including closed deep chipping and slurry treatment, watering, curing cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	Sqm	100.87	220.00	22191.00

8	Supplying, fitting and fixing vitrified tile (Printed) in floors of size 600mm x 600mm of approved make conforming to IS : 13755 laid on 20 mm thick cement mortar (1:4) (1 cement :4 course sand) and filling joints with white cement of approved quality including cost of all materials, labour T&P etc. required	Sqm	100.87	1211.90	122240.00
9	Fixing Vitrified tiles (size 600mmx600mm) (Printed) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.	Sqm	7.7	1355.20	10435.00
10	Fixing Ceramic tiles (30cmx30cm / 40cm x 40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13753) in floor and tread steps on 20mm thick cement plaster (1:4) jointed with neat cement slurry mixed with pigments to match the shades of	Sqm	13.263	926.80	12292.00
11	Fixing Ceramic tiles (20cmx30cm / 20cm x 20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in dados skirting and risers of steps on 12mm thick cement plaster (1:4) jointed with neat cement slurry mixed with pigments to match the shades of the tiles including cost of tiles.	Sqm	41.22	1012.80	41748.00
12	Finishing to the exposed surfaces of wall with weather coat of any approved shade	Sqm	101.69	106.30	10810.00
13	Finishing surface of walls with acrylic based wall putty & making smooth to receive painting including cost of scaffolding etc. with cost of all materials, labour T&P etc. complete.	Sqm	386.51	112.10	43328.00
14	Priming 1 coat with wall primer water bond cement primer including all labour, Materials, T&P etc Complete	Sqm	339.47	83.90	28482.00
15	Finishing wall with plastic imulsion paints 2 coat with wall with any approved paints including all labour, Materials, T&P etc Complete	Sqm	284.72	106.40	30294.21
16	Cost of MS Grill,Door & Windows	Kg	579.6	110.00	63756.00
17	Priming 1 coat with red oxide primer	Sqm	10.08	76.80	774.00
18	Painting 2 coat with approved paints with iron works	Sqm	10.08	191.30	1928.00

19	Cost of UPVC Windows	sqm	10.08	4960.97	50007
20	Cost of Aluminium door	No.	2	5000	10000
21	Display Board	No.	1	5000.00	5000.00
Total					1266032

(Extra CGST&SGST Will paid as applicable)

S. Swan (AE)
30/12/25
Asst. Engineer
Laikera Block


Asst. Exp. Engineer
Laikera Block


BDO
Laikera Block

The Tenderer are required to put their percentage of rate in the blank space given below, failing which the tender document will be rejected.

My/Our quoted rate is _____%(Figure) _____ (In words)

*Less than/Excess over/ Equal to the amount put to tender.

Total number of Items:.....	
Number of Corrections:.....	
Number of interpolation:.....	
Number of over writings:.....	
E.M.D Funnished/EMD Exempted	
(A)Demand Draft No.....	
(B)Ammount Rs.....	
Copy of PAN card:furnished/not furnished	
Copy of GST Registration:furnished/not furnished	
Copy of Contractor's Licensce:furnished/not furnished	
Copy of Experience certificate:furnished/not furnished	
Total No of sheets in the Tender Papers:.....	

Full Signature of Contractor

Signature of the Bidder/Tenderer


Signature of the B.D.O
Laikera Block