

BOQ

Tender Inviting Authority: BDO, Lakhanpur

Name of Work: Construction of Addl. Class Room at Govt. High School, Pipilikani

PRICE SCHEDULE

(this BOQ template must be modified/ replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender . Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	Quantity	Units	Estimated Rate	Total Amount Without Taxes	Total Amount in Words
1	Earth work in excavation in foundation in all kinds of soil with all leads and lifts including dressing and levelling the bed in layers not exceeding 0.3 m in depth including dewatering if necessary with cost of all labour and T & P work etc. Complete as per direction of Engineer-in-charge					
		64.48	cum	276.90	17855.00	
2	Supplying filling in F & P with clean course good river sand including watering, ramming, poking & compacting & cost, conveyance royalties, taxes of all materials, labour, T & P etc. Complete as per direction of Engineer-in-Charge					
		36.66	cum	767.50	28137.00	
3	Providing and laying PCC of (1:3:6) with 2.5cm to 4cm size crusher broken hard black granite metal with cost, conveyance, royalties, taxes of all materials, all labour, T & P etc. Complete as per direction of Engineer-in-charge					
		16.31	cum	5904.50	96302.00	
4	Providing and laying RCC work in M-20 grade with 20mm and down grade black hard granite crusher broken stone chips of approved quality from quarry with smooth centering and shuttering hoisting and laying in layers including cost. Conveyance, royalty and taxes of all materials, labour, T & P etc. complete as per direction of the Engineer-in-charge					
A	Column Base footing					
		20.80	Cum	6366.85	132430.00	


B	Plinth Bend				
		3.00	Cum	7238.00	21714.00
C	Lintel Beam Column Above Plinth, Wall beam & Room Beam				
		3.00	Cum	14081.30	42244.00
RCC M 25					
D	Roof Slab & Chajja				
		10.12	Cum	13621.50	137850.00
		1.3	Cum	1213.67	1578.00
E	Column and roof beam				
		11.26	Cum	15634.00	176039.00
5	Providing MS Reinforcement for RCC work including cutting, bending, binding & tying the grills & placing in position with cost of MS Rod and binding wire of 18 to 20 gauge including cost of all materials, labour, T & P etc. Complete as per direction of the Engineer-in-Charge (G. Floor)				
		44.53	Qnt.	6815.14	303492.00
6	Brick work with Fly Ash bricks of size 23cmX11cmX8cm and crushing strength not less than 75kg/cm ² in C.M.(1:6) in foundation and plinth including all charges				
		33.49	Cum	5426.70	181740.00
7	Brick work with Fly Ash bricks of size 23cmX11cmX8cm and crushing strength not less than 75kg/cm ² in C.M.(1:4) in super structure including all charges (G. Floor)				
		27.70	Cum	5628.70	155915.00
8	12mm (1/2") thick cement plaster (1:6) over brick work (G.Floor)				
		84.32	Sqm	189.70	15996.00

9	Providing 16 mm thick cement plaster in CM (1:6) finished smooth to inside surface including cost conveyance, royalty, taxes of all materials, labour, T & P etc. complete as per direction of Engineer-in-Charge (G.Floor)	99.86	Sqm	274.00	27362.00	
10	6mm thick cement plaster (1:4) to RCC surfaces finished smooth including closed deep chipping and slurry treatment (G.Floor)	90.30	Sqm	212.20	19162.00	
11	Supplying fitting and fixing vetrified tile in floors of size 600mmX 600mm of approved make confirming to IS 13755 laid on 20mm thick cement mortar (1:4) (1cement:4course sand) and filling joints with white cement of approved quality including cost of all materials, labour T & P etc required for the work all complete as per direction of the Engineer-in-Charge (For new work only)	98.55	Sqm	1144.50	112790.00	
12	Finishing Surface Of Walls With Cement Based Wall Putty & Making Smooth To Recive Painting Including Cost Of Scaffolding Etc. With Cost Of All Material & Labour	181.80	Sqm	89.60	16289.00	
13	Supplying fitting fixing MS Door and Windows including transport taxes of all materials in G. Floor	472.50	KG	100.00	47250.00	
14	Finishing walls with water proofing weather coat paint	84.32	Sqm	97.30	8204.00	
15	Providing 20 mm thick cement plaster in CM (1:4) finished smooth to inside surface including cost conveyance, royalty, taxes of all materials, labour, T & P etc. complete as per direction of Engineer-in-Charge (G.Floor)	99.73	Sqm	285.30	28453.00	

16	Supplying fitting and fixing vetrified tile in Dados of approved make confirming to IS 13755 laid on 20mm thick cement mortar (1:4) (1cement:4course sand) and filling joints with white cement of approved quality including cost of all materials, labour T & P etc required for the work all complete as per direction of the Engineer-in-Charge (For new work only)	8.36	Sqm	1731.01	14471.00
17	Painting two coats with approved paint on new wood/Iron work	23.78	Sqm	186.90	4444.00
18	Painting two coat with SE paint over a coat of primer with approved shade of approved quality including cost of all materials & labour with T & P etc. complete (G Floor)	266.12	Sqm	80.60	21449.00
19	Fire Fighting Arrengement				7000.00
20	Provision for Black Board of size 12.00X4.00 ft size				8000.00
21	Add towards cost of electrification and sanitary fitting with all material			L/S	74271.00
22	Provision For const of Display Board			L/S	5000.00
				Total	1705437.00

(Rupees Seventeen Lakhs Five Thousand Four Hundred Thirty Seven) Only


Assistant Executive Engineer
Lakhanpur Block


AE/JE/GRTA
Lakhanpur Block
APPROVED FOR 22 (Twenty Two) ITEMS ONLY


Block Development Officer
Lakhanpur

My/our quoted rate is % (both in figures and words) excess over / less than / equal to the above estimated cost.

Signature of Tenderer

NOTES :-

1. The contractor should not write anything excepting quoting of percentage and in any case
2. Percentage quoted by the tenderer shall be accurately filled in words and in figures..
3. Strike out which is not applicable. If the tenderer quotes the percentage without mentioning
4. Percentage should be quoted up to (one) digit after the decimal point. If the tenderer writes more
5. Rate of all items are inclusive of cost, carriage, royalty, cess and other taxes of materials.

Tenderer

No. of corrections.....
No. of Over writings.....
No. of Interpolations.....