

Imp of road from Anganwadi chowk to Ankuli village road.

BILL OF QUANTITY

I. No.	Item of Work	Quantity to be executed	Unit	Rate	Amount
1	2	3	4	5	6
	Earth work in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all	32.62	Cu.m	276.89	9032.00
2	Filling foundation and plinth with sand including cost conveyance taxes of all material and labour T&P etc. complete in all respect.	4.99	Cu.m	995.08	4965.00
3	Cement concret (1:3:6) using 4cm size hg metals of approved quality including cost, conveyance, taxes, royalties of all materials, watering &	30.00	Cu.m	5909.35	177281.00
4	R.C.C.M-200 using 20 mm and down graded hard granite crusher broken chips, etc.	3.99	Cu.m	6235.11	24878.00
5	Straightening, cutting, bending, binding for steel rods, cranking, hooking, tying the grills & placing in proper position for R.C.C work,	4.00	One Quintal	8737.10	34948.00
6	Cement concrete (1:2:4) with 1.2cm size CB Chips including cost, conveyance & royalty of materials. all labour charges, cess required for the work etc. complete.	1.52	Cu.m	7740.55	11766.00
7	Rigid smooth centering & shuttering-				
	a) Abutment	88.85	1Sq.m	245.19	21785.00
	b) Deck Slab	11.64	1Sq.m	740.80	8623.00
8	Collecting ,Conveyence,Stacking of good Laterite morum at road side with box heaps of1.5m*1.5m*0.5m to be mesured at 1cum	727.00	Cu.m	462.82	336470.00
9	Conveying from stacks and spreading moorum on sub base watering and Compacting with PRR including and Running Charges of PRR etc	663.00	Cu.m	507.68	336592.00

10	Collection ,conveyance ,Stacking of 4cm size hard granite stone on Road site with Box heaps of 1.5m*1.5m*0.5m to be mesured as 1cum	255.00	Cu.m	1823.26	464931.00
11	Conveying from Stacks and Spreading Over size 50mm To 40mm for H.S metaling to void with small stone and Packing the same to proper camber Conveyeing from stacks & watering turf edging etc and Consoldition with PRR	255.00	Cu.m	955.52	243658.00
12	Cost of Transperancy board	1.00	Each	5000.00	5000.00
				GRAND TOTAL	1679929.00

(RUPEES SIXTEEN LAKH SEVENTYNINE THOUSAND NINE HUNDRED TWENTY NINE) ONLY


Assistant Executive Engineer
Lakhanpur Block


AE/JE/GRTA
Lakhanpur Block

APPROVED FOR 12 (Twelve) ITEMS ONLY

My/our quoted rate is % (both in figures and

Signature of Tenderer

NOTES :-

1. The contractor should not write anything excepting quoting of percentage and in any case anything else
2. Percentage quoted by the tenderer shall be accurately filled in words and in figures..
3. Strike out which is not applicable. If the tenderer quotes the percentage without mentioning excess or less, it
4. Percentage should be quoted up to (one) digit after the decimal point. If the tenderer writes more than 1 digit
5. Rate of all items are inclusive of cost, carriage, royalty, cess and other taxes of materials.

Tenderer

No. of corrections.....
 No. of Over writings.....
 No. of Interpolations.....

Contractor