


BILL OF QUANTITY
RENOVATION OF GHUMER BANDH AT CHARPALI

SL NO	ITEM OF WORK	QUANTITY	UNIT	RATE	AMOUNT
1	Excavation, loading and carriage by mechanical means all kinds of soil, including stoney earth, gravel and moorum etc interspread with	9611.80	Cum	115.89	Rs. 11,13,912.00
2	Earth work excavation in hard soil within Initial lead and initial lift including rough dressing and levelling the foudation bed and depositing the excavted earth away from work site etc.compelte	63.46	Cum	274.15	Rs. 17,397.00
4	Filling foundation and plinth with well watered and rammed sand including all cost, conveyance and royalty of all materials etc.	28.84	Cum	985.23	Rs. 28,414.00
5	CC(1:3:6) using 40 mm size CBG mental in foudation including all cost, conveyance, curing and royalty etc complete.	44.84	Cum	6349.63	Rs. 2,84,737.00
6	Cement concrete(1.2:4) using 12mm size hard granite chips of approved quality including cost, conveyance, taxes & royalty of all materials and	3.33	Cum	7226.68	Rs. 24,065.00
7	Rigid and smooth Centering and shuttering for R.C.C.Works and dismantling then after casting including cost of all materials complete.	48.18	Cum	246.15	Rs. 11,859.00
8	12mm.thick Cement Plaster in C.M.(1:6) including cost, carriage & royalty etc. complete.	109.77	Cum	195.91	Rs. 21,505.00
9	Display board				Rs. 5,000.00
10	Chair				Rs. 30,000.00
	TOTAL				Rs. 15,36,889.00


ASST. EXE.ENGINEER
Lakhanpur Block


JUNIOR ENGINEER
Lakhanpur Block


Block Development Officer
Lakhanpur Block