


# IMP. OF ROAD FROM PIPLIMAL GOUDPADA TO GANJAMUNDA ROAD

## BILL OF QUANTITY

SL NO	ITEM OF WORK	QUANTITY	UNIT	RATE	AMOUNT
1	Earth work excavation in hard soil within Initial lead and initial lift including rough dressing and levelling the foudation bed and depositing the excavated earth away from work site etc.compelte	98.62	Cum	230.74	Rs. 22,756.00
2	Filling foundation and plinth with well watered and rammed sand including all cost, conveyance and royalty of all materials etc.	98.98	Cum	971.13	Rs. 96,122.00
3	CC(1:3:6) using 40 mm size CBG mental in foudation including all cost, conveyance, curing and royalty etc complete.	131.50	Cum	5829.97	Rs. 766,641.00
4	Cement concrete(1:2:4) using 12mm size hard granite chips of approved quality including cost, conveyance, taxes & royalty of all materials and	79.11	Cum	7457.81	Rs. 589,987.00
5	Rigid and smooth Centering and shuttering for R.C.C.Works and dismantling then after casting including cost of all materials complete.	158.95	Cum	248.67	Rs. 39,526.00
6	Display board				Rs. 5,000.00
<b>TOTAL</b>					<b>Rs. 1,520,032.00</b>

(Rupees Fifteen Lakhs Twenty Thousands Thirty Two) Only

  
 Juniou/Asst. Engineer  
 Lakhanpur Block

  
 Asst. Executive Engineer  
 Lakhanpur Block

  
 Block Development Officer  
 Lakhanpur

My quoted Rate is .....%( write in word )  
 excess over/ less than/ equal to the above tendered value.

**Note:-**

The Tenderer/ Bidder/Quotationer should not write anything else except quoting percentage rate.  
 Any conditional rate quoted is not accepted.

Strikeover on the rate quoted is liable to rejection.

Percentage rate quoted should be within 2(Two) digit after decimal point.

Rate of all items are inclusive of cost, carriage and royalty but excluding GST of materials.

Number of correction made.....

Number of overwriting made.....