

BILL OF QUANTITY

Name of the Work- Improvement of road from Grindola Talipada to PMGSY Road Katatikra

SL NO	ITEM OF WORK	QUANTITY	UNIT	RATE	AMOUNT
1	Earth work excavation in hard soil within Initial lead and initial lift including rough dressing and levelling the foudation bed and depositing the excavted earth away from work site etc.compelte	163.00	Cum	230.74	Rs. 37,611.00
2	Filling foundation and plinth with well watered and rammed sand including all cost, conveyance and royalty of all materials etc.	111.98	Cum	720.11	Rs. 1,11,429.00
3	CC(1:3:6) using 40 mm size CBG mental in foudation including all cost,conveyance, curing and royalty etc complete.	133.99	Cum	5838.80	Rs. 7,82,318.00
4	Cement concrete(1:2:4) using 12mm size hard granite chips of approved quality including cost, conveyance, taxes & royalty of all materials and labour etc.. complete in all respect.	118.99	Cum	7393.09	Rs. 8,35,718.00
5	Rigid and smooth Centering and shuttering for R.C.C.Works and dismantling then after casting including cost of all materials complete.	260.80	Cum	248.61	Rs. 64,838.00
6	Display board				Rs. 5,000.00
	TOTAL				Rs. 18,36,914.00


Assistant Executive Engineer
Lakhanpur Block


AE/JE/GPTA
Lakhanpur Block

APPROVED FOR 6 (Six) ITEMS ONLY


Block Development Officer
Lakhanpur

My/our quoted rate is % (both in figures and words) excess over / less than / equal to the above estimated cost.

Signature of Tenderer



Signature of Tenderer

NOTES :-

1. The contractor should not write anything excepting quoting of percentage and in any case anything
2. Percentage quoted by the tenderer shall be accurately filled in words and in figures..
3. Strike out which is not applicable. If the tenderer quotes the percentage without mentioning excess or
4. Percentage should be quoted up to (one) digit after the decimal point. If the tenderer writes more than
5. Rate of all items are inclusive of cost, carriage, royalty, cess and other taxes of materials.

Tenderer

No. of corrections.....
No. of Over writings.....
No. of Interpolations.....

