

ny case

Improvement of CC road PMGSY Road to Jaybudia to Patarfandi, Kudaloi GP					
BILL OF QUANTITY					
Sl. No.	Item of Work	Quantity to be executed	Unit	Rate	Amount
1	2	3	4	5	6
1	Earth work excavation in hard soil within initial lead and initial lift including rough dressing and levelling the foundation bed and depositing the excavated earth away from work site etc complete	126.00	Cum	230.74	29074.00
2	Filling foundation and plinth with well watered and rammed sand including all cost conveyance and royalty of all materials etc	86.56	Cum	720.11	62334.00
3	CC(1:3:6) using 40 mm size CBG mental in foundation including all cost, conveyance, curing and royalty etc complete	103.57	Cum	5838.80	604736.00
4	Cement Concrete (1:2:4) using 12 mm size hard granite chips of approved quality including cost, conveyance, taxes & royalty of all materials	91.98	Cum	7393.09	680017.00
5	Rigid and smooth centering and shuttering for RCC works and dismantling then after casting including cost of all materials complete	201.60	Cum	248.61	50120.00
6	Cost of Display board				5000.00
				GRAND TOTAL	1431281.0

(RUPEES FOURTEEN LAKHS THIRTY ONE THOUSAND TWO HUNDRED EIGHTY ONE) ONLY


Assistant Executive Engineer
Lakhanpur Block


AE/JE/GPTA
Lakhanpur Block

APPROVED FOR 06 (SIX) ITEMS ONLY


Block Development Officer
Lakhanpur

My/our quoted rate is % (both in figures and words) excess over / less than / equal to the above estimated cost.

Signature of Tenderer



NOTES :-

1. The contractor should not write anything excepting quoting of percentage and in any case
2. Percentage quoted by the tenderer shall be accurately filled in words and in figures..
3. Strike out which is not applicable. If the tenderer quotes the percentage without mentioning
4. Percentage should be quoted up to (one) digit after the decimal point. If the tenderer writes
5. Rate of all items are inclusive of cost, carriage, royalty, cess and other taxes of materials.

Tenderer

No. of corrections.....

No. of Over writings.....

No. of Interpolations.....

