


IMP. OF ROAD FROM KIRARAMA TO DHUBENTIPI

BILL OF QUANTITY

SL NO	ITEM OF WORK	QUANTITY	UNIT	RATE	AMOUNT
1	Earth work excavation in hard soil within Initial lead and initial lift including rough dressing and levelling the foudation bed and depositing the excavated earth away from work site etc.compelte	118.98	Cum	230.74	Rs. 27,453.00
2	Filling foundation and plinth with well watered and rammed sand including all cost, conveyance and royalty of all materials etc.	173.91	Cum	1107.93	Rs. 192,684.00
3	CC(1:3:6) using 40 mm size CBG mental in foudation including all cost,conveyance, curing and royalty etc complete.	142.21	Cum	5781.17	Rs. 822,167.00
4	Cement concrete(1:2:4) using 12mm size hard granite chips of approved quality including cost, conveyance, taxes & royalty of all materials and	70.46	Cum	7341.67	Rs. 517,265.00
5	M20 with 20mm size C.B. Chips downgraded to 10 mm chips for R.C.C work including hoisting and laying with of approved quality including cost,	3.40	Cum	5990.54	Rs. 20,380.00
6	Labour for MS reinforcement for RCC work including cutting,bending ,binding and tying the grills and placing in position including cost of	3.40	Qntl	8890.07	Rs. 30,244.00
7	Rigid and smooth Centering and shuttering for R.C.C.Works and dismantling then after casting including cost of all materials complete.				
	(A) Roof slabs, Chajjas	15.84	Sqm	747.35	Rs. 11,838.00
	(B) Plinth band ,Base of columns upto Plinth	189.62	Sqm	246.21	Rs. 46,686.00
8	Labour of spreading moorum including cost and conveyance of moorum.etc Completed	14.60	Cum	593.05	Rs. 8,659.00
9	Display board				Rs. 5,000.00
	TOTAL				Rs. 1,682,376.00

(Rupees Sixteen Lakhs Eighty Two Thousands Three Hundreds Seventy Six) Only


Junior/Asst. Engineer
Lakhanpur Block


Asst. Executive Engineer
Lakhanpur Block


Block Development Officer
Lakhanpur

My quoted Rate is%(write in word)
 excess over/ less than/ equal to the above tendered value.

Note:-

The Tenderer/ Bidder/Quotationer should not write anything else except quoting percentage rate.

Any conditional rate quoted is not accepted.

Strikeover on the rate quoted is liable to rejection.

Percentage rate quoted should be within 2(Two) digit after decimal point.

Rate of all items are inclusive of cost, carriage and royalty but excluding GST of materials.

Number of correction made.....

Number of overwriting made.....

