

IMP. OF ROAD FROM LIAKHAI ROAD TO DHARUAMUNDA

BILL OF QUANTITY

| SL NO | ITEM OF WORK | QUANTITY | UNIT | RATE | AMOUNT |
|-------|---|----------|------|---------|-------------------------|
| 1 | Earth work excavation in hard soil within Initial lead and initial lift including rough dressing and levelling the foudation bed and depositing the excavted earth away from work site etc.compelte | 118.76 | Cum | 230.74 | Rs. 27,403.00 |
| 2 | Filling foundation and plinth with well watered and rammed sand including all cost, conveyance and royalty of all materials etc. | 119.19 | Cum | 976.43 | Rs. 116,381.00 |
| 3 | CC(1:3:6) using 40 mm size CBG mental in foudation including all cost,conveyance, curing and royalty etc complete. | 158.34 | Cum | 5851.42 | Rs. 926,514.00 |
| 4 | Cement concrete(1:2:4) using 12mm size hard granite chips of approved quality including cost, conveyance, taxes & royalty of all materials and | 95.27 | Cum | 7477.92 | Rs. 712,421.00 |
| 5 | Rigid and smooth Centering and shuttering for R.C.C.Works and dismantling then after casting including cost of all materials complete. | 261.00 | Cum | 248.67 | Rs. 64,903.00 |
| 6 | Display board | | | | Rs. 5,000.00 |
| | TOTAL | | | | Rs. 1,852,622.00 |

(Rupees Eighteen Lakhs Fifty Two Thousands Six HundredsTwenty Two) Only


Junior/Asst. Engineer
Lakhanpur Block


Asst. Executive Engineer
Lakhanpur Block


Block Development Officer
Lakhanpur

My quoted Rate is%(write in word)
excess over/ less than/ equal to the above tendered value.

Note:-

The Tenderer/ Bidder/Quotationer should not write anything else except quoting percentage rate.

Any conditional rate quoted is not accepted.

Strikeover on the rate quoted is liable to rejection.

Percentage rate quoted should be within 2(Two) digit after decimal point.

Rate of all items are inclusive of cost, carriage and royalty but excluding GST of materials.

Number of correction made.....

Number of overwriting made.....