

**IMPROVEMENT OF ROAD FROM SARANGDERA SCHOOL TO LELHERJORE THEBRA****BILL OF QUANTITY**

Sl. No.	Item of Work	Quantity to be executed	Unit	Rate	Amount
1	2	3	4	5	6
1	Earth work in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing & leveling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering, if necessary from foundation complete as directed by Engineer-in-charge	1484.40	Cu.m	230.74	342510.00
2	Filling foundation and plinth with sand including cost conveyance taxes of all material and labour T&P etc. complete in all respect.	16.74	Cu.m	985.08	16490.00
3	Cement concret (1:3:6) using 4cm size hg metals of approved quality including cost, conveyance, taxes, royalties of all materials, watering & curing for 28 days & cost of all labour with T&P etc. complete.	36.82	Cu.m	6059.79	223121.00
4	R.C.C. M25 using 20mm and down graded hard granite crusher broken chips including cost, conveyance and royalty of materials curing etc. complete as per direction of Engineer-in-charge.	8.00	Cu.m	6448.09	51585.00
5	Cost of steel including all cost & carriage including labour charges and as per direction of Engineer-in-charge.	8.00	Cu.m	9096.60	72773.00
6	Rigid and Smooth Centering and shuttering for RCC Works including false works and dismantling them after casting including cost of materials etc. complete.				
a)	Abutment/Wing Wall	110.48	Sqm	249.62	27578.00
b)	Slab	32.04	Sqm	710.99	22780.00
7	Collecting, conveying, stacking Hand broken hard granite metal (40mm) size on road side in regular box heaps of size (1.5x1.5x0.44m)=1 cum, including all cost,	227.53	Cu.m	1876.26	426905.00



8	Collecting, conveying, stacking of moorum at road side in regular box heaps of size (1.5x1.5x0.44m)=1 cum, including all cost,	618.56	Cu.m	532.25	329229.00
9	Conveying from stack and laying moorum in sub-base in layers not exceeding 15cm including watering and consolidation with PRR including hire & running charges.	357.38	Cu.m	485.51	173512.00
10	Conveying from stacks & spreading Hand Brocken hard granite metal (40mm) size on road surface with proper camber and consolidation with PRR including hire and running charges of PRR	199.09	Cu.m	874.55	174114.00
11	Cost of Transperancy board	1.00	Each	5000.00	5000.00
				<b>GRAND TOTAL</b>	<b>1865597.0</b>

(RUPEES EIGHTEEN LAKHS SIXTY FIVE THOUSAND FIVE HUNDRED NINTY SEVEN) ONLY

  
**Assistant Executive Engineer**  
**Lakhanpur Block**

  
**AE/JE/GPTA**  
**Lakhanpur Block**

**APPROVED FOR 11 (ELEVEN) ITEMS ONLY**

  
**Block Development Officer**  
**Lakhanpur**

My/our quoted rate is ..... % (both in figures and words) excess over / less than / equal to the above estimated cost.

**Signature of Tenderer**

**NOTES :-**

1. The contractor should not write anything excepting quoting of percentage and in any case
2. Percentage quoted by the tenderer shall be accurately filled in words and in figures..
3. Strike out which is not applicable. If the tenderer quotes the percentage without mentioning
4. Percentage should be quoted up to (one) digit after the decimal point. If the tenderer writes
5. Rate of all items are inclusive of cost, carriage, royalty, cess and other taxes of materials.

**Tenderer**

No. of corrections.....  
 No. of Over writings.....  
 No. of Interpolations.....