


CONSTRUCTION OF PAVOUR BLOCK AT WEEKLY MARKET JAMGAON

BILL OF QUANTITY

SL NO	ITEM OF WORK	QUANTITY	UNIT	RATE	AMOUNT
1	Earth work excavation in hard soil within Initial lead and initial lift including rough dressing and levelling the foudation bed and depositing the excavated earth away from work site etc.compelte	225.52	Cum	230.74	Rs. 52,037.00
2	Filling foundation and plinth with well watered and rammed sand including all cost, convayance and royalty of all materials etc.	147.32	Cum	995.08	Rs. 1,46,598.00
3	CC(1:3:6) using 40 mm size CBG mental in foudation including all cost,conveyance, curing and royalty etc complete.	13.60	Cum	5838.80	Rs. 79,402.00
4	Providing and laying 80mm thick.factory made cement concrete interlocking paver block of M - 30 grade made by block making machine with	1382.57	Cum	1012.00	Rs. 13,99,156.00
5	Display board				Rs. 5,000.00
	TOTAL				Rs. 16,82,193.00

Rupees Sixteen Lakh Eighty Two Thousand One HundredNinty Three only


ASST. EXE.ENGINEER
 Lakhanpur Block


JUNIOR ENGINEER
 Lakhanpur Block

APPROVED FOR 6 (Six) ITEMS ONLY


Block Development Officer
 Lakhanpur Block

My/our quoted rate is.....% (both in figure and words) excess over /less than / equal to the above estimated cost.

Signature of Tendered

NOTES :-

1. The contractor should not write anything excepting quoting of percentage and in any case.
2. Percentage quoted by the tenderer shall be accurately filled in words and in figure..
3. Strike out which is not applicable. If the Tenderer quotes the percentage without mentioning.
4. Percentage should be quoted up to (one) digit after the decimal point. If the tenderer writes.
5. Rate of all items are inclusive of cost, carriage, royalty, cess and other taxes of material.

Tenderer

No. of Correction

No of Over writing

No. of Interpolations.....