

**IMPROVEMENT OF ROAD FROM ADHAPADA SHIVA MANDIR TO KHANDSA ROAD**

**BILL OF QUANTITY**

SL NO	ITEM OF WORK	QUANTITY	UNIT	RATE	AMOUNT
1	Earth work excavation in hard soil within Initial lead and initial lift including rough dressing and levelling the foudation bed and depositing the excavted earth away from work site etc.compelte	125.25	Cum	230.74	Rs. 28,901.00
2	Filling foundation and plinth with well watered and rammed sand including all cost, conveyance and royalty of all materials etc.	86.05	Cum	995.08	Rs. 85,624.00
3	CC(1:3:6) using 40 mm size CBG mental in foudation including all cost,conveyance, curing and royalty etc complete.	102.96	Cum	5838.80	Rs. 6,01,140.00
4	Cement concrete(1:2:4) using 12mm size hard granite chips of approved quality including cost, conveyance, taxes & royalty of all materials and	68.57	Cum	7393.09	Rs. 5,06,974.00
5	Rigid and smooth Centering and shuttering for R.C.C.Works and dismantling then after casting including cost of all materials complete.	137.78	Cum	248.61	Rs. 34,253.00
6	Display board				Rs. 5,000.00
	<b>TOTAL</b>				<b>Rs. 12,61,892.00</b>

(Rupees Twelve Lakh Sixty One Thousand Eight Hundred Ninty Two only)

  
**ASST. EXE.ENGINEER**  
Lakhanpur Block

  
**JUNIOR ENGINEER**  
Lakhanpur Block

**APPROVED FOR 6 (Six) ITEMS ONLY**

  
**Block Development Officer**  
Lakhanpur Block

My/our quoted rate is.....% (both in figure and words) excess over /less than / equal to the above estimated cost.

**Signature of Tendered**

**NOTES :-**

1. The contractor should not write anything excepting quoting of percentage and in any case.
2. Percentage quoted by the tenderer shall be accurately filled in words and in figure..
- 3.Strike out which is not applicable. If the Tenderer quotes the percentage without mentioning.
4. Percentage should be quoted up to (one) digit after the decimal point. If the tenderer writes.
5. Rate of all items are inclusive of cost, carriage, royalty, cess and other taxes of material.

**Tenderer**

No. of Correction .....

No of Over writing .....

No. of Interpolations.....